

Addendum # 1 RFP 24-013 OHS Baseball Field

Scope of Work

1. The existing irrigation system is 2" schedule 40 PVC pipe, reducing down to 1" at the irrigation head. Any additional irrigation lines, or irrigation heads that may need to be added for appropriate coverage will be installed by the owner. Contractor will work with the owner to mark/ identify new infield locations if additional irrigation is needed.
2. Contractor is responsible to provide two mowings of the new sod before turning over to the owner to maintain.
3. Contractor is responsible to repair any damage to grass, concrete, fencing while exporting and importing materials to the construction area.