
STAGE LIGHTING CONTROLS UPGRADE

OGDEN SCHOOL DISTRICT

SEPTEMBER 2023

BNA CONSULTING

635 South State Street Salt Lake City, Utah 8411



PROJECT DIRECTORY

PROJECT: STAGE LIGHTING CONTROLS UPGRADE

MOUND FORT MIDDLE SCHOOL

1400 MOUND FORT DRIVE

Ogden, UT 84404

OWNER: **OGDEN SCHOOL DISTRICT**

> 1950 Monroe Blvd Ogden, Utah 84401

Jared Cherry (801) 737-8845

ELECTRICAL BNA CONSULTING ENGINEER:

635 South State Street

Salt Lake City, Utah 84111 801 532 2196 fax 801 532-2305

Richard Wardle richard@bnaconsulting.com Greg Brenchley gbrenchly@bnaconsulting.com **BLANK PAGE**

DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

000000 **COVER SHEET**

000002 PROJECT DIRECTORY 000003 **TABLE OF CONTENTS**

AIA Documents

a. A701-1997 - Instructions to Bidders

b. A201-2007 - General Conditions of the Contract for Construction

c. A310-1970 - Bid Bond

d. A312-1984 - Payment Bond & Performance Bond

e. G701-2001 - Change order

f. G702-1992 – Application and Certificate for Payment

g. G704-2000 - Certificate of Substantial Completion

h. G706A - Contractor's Affidavit of Release of Liens

i. G707 - Consent of Surety to Final Payment

j. G710 - Architect's Supplemental Instructions

SAMPLE AGREEMENT

SUPPLEMENTARY GENERAL CONDITIONS OF THE CONTRACT

TAX EXEMPT FORM

ASBESTOS COMPLIANCE MANIFEST

CONSTRUCTION MATERIAL ASBESTOS STATEMENT

STATE CONSTRUCTION CONTRACTS AND DRUG AND ALCOHOL TESTING

ASBESTOS SURVEY, NESHAP, DATED JULY 27, 2012

DIVISION 01 - GENERAL REQUIREMENTS

011000	SUMMARY
011000	SOMMAN
012600	CONTRACT MODIFICATION PROCEDURES
012900	PAYMENT PROCEDURES
013300	SUBMITTAL PROCEDURES
015000	TEMPORARY FACILITIES AND CONTROLS
016000	PRODUCT REQUIREMENTS
017300	EXECUTION
017700	CLOSEOUT PROCEDURES

DIVISION 26 – ELECTRICAL

260500 260507	ELECTRICAL GENERAL PROVISIONS ELECTRICAL CONNECTIONS FOR EQUIPMENT
260519	CONDUCTORS AND CABLES
260526	GROUNDING
260529	SUPPORTING DEVICES
260533	ELECTRICAL BOXES AND FITTINGS
260536	RACEWAY SYSTEMS
260548	ELECTRONICAL SEISMIC CONTROL
260553	ELECTRONICAL IDENTIFICATION
283111	FIRE ALARM AND DETECTION SYSTEMS

TABLE OF CONTENTS 1 **BLANK PAGE**

TABLE OF CONTENTS 2

DIVISION 01 - GENERAL REQUIREMENTS

011000	SUMMARY
012600	CONTRACT MODIFICATION PROCEDURES
012900	PAYMENT PROCEDURES
013300	SUBMITTAL PROCEDURES
015000	TEMPORARY FACILITIES AND CONTROLS
016000	PRODUCT REQUIREMENTS
017300	EXECUTION
017700	CLOSEOUT PROCEDURES

BLANK PAGE

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

- 1. Project information.
- 2. Work covered by Contract Documents.
- 3. Access to site.
- 4. Coordination with occupants.
- 5. Work restrictions.
- 6. Specification and drawing conventions.
- 7. Miscellaneous provisions.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

1.2 PROJECT INFORMATION

A. Project Identification: STAGE LIGHTING CONTROLS UPGRADE

MOUND FORT MIDDLE SCHOOL

1400 Mound Fort Drive Ogden, UT 84404

B. Owner: OGDEN SCHOOL DISTRICT

1950 Monroe Blvd Ogden, Utah 84401

C. Electrical Engineer: BNA CONSULTING, INC.

635 South State Street Salt Lake City, Utah 84111

801.532.2196, Richard Wardle, Greg Brenchly

1.3 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of Stage Lighting Controls Upgrade is defined by the Contract Documents and consists of the following:
 - 1. As shown on the drawings and as specified here-in.
- B. Type of Contract.
 - 1. Project will be constructed under a single prime contract.

1.4 ACCESS TO SITE

- A. General: Contractor shall have limited use of Project site for construction operations as indicated on the Drawings by the Contract limits and as indicated by requirements of this Section.
- B. Use of Site: Limit use of Project site to work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
 - Limits: Confine construction operations to designated areas necessary for the completion of the work.
 - 2. Driveways, Walkways and Entrances: Keep driveways and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- C. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.

1.5 COORDINATION WITH OCCUPANTS

- A. Owner Limited Occupancy of Completed Areas of Construction: Owner reserves the right to occupy and to place and install equipment in completed portions of the Work, prior to Substantial Completion of the Work, provided such occupancy does not interfere with completion of the Work. Such placement of equipment and limited occupancy shall not constitute acceptance of the total Work.
 - 1. Engineer will prepare a Certificate of Substantial Completion for each specific portion of the Work to be occupied prior to Owner acceptance of the completed Work.
 - 2. Obtain a Certificate of Occupancy from authorities having jurisdiction before limited Owner occupancy.
 - 3. Before limited Owner occupancy, mechanical and electrical systems shall be fully operational, and required tests and inspections shall be successfully completed. On occupancy, Owner will operate and maintain mechanical and electrical systems serving occupied portions of Work.
 - 4. On occupancy, Owner will assume responsibility for maintenance and custodial service for occupied portions of Work.

1.6 WORK RESTRICTIONS

- A. Work Restrictions, General: Comply with restrictions on construction operations.
 - 1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.
- B. On-Site Work Hours: Limit work in the existing building to normal business working hours of 7:00 a.m. to 6:00 p.m., Monday through Friday, unless the work is to be completed during the

time when school is in session, all work shall be completed after hours and on weekends., Coordinate with the School District.

- C. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:
 - 1. Notify Engineer not less than two days in advance of proposed utility interruptions.
- D. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner occupancy with Owner.
 - 1. Notify Engineer not less than two days in advance of proposed disruptive operations.
 - 2. Obtain Engineer's written permission before proceeding with disruptive operations.
- E. Nonsmoking Building: Smoking is not permitted within the building or on school property.
- F. Controlled Substances: Use of tobacco products and other controlled substances on Project site is not permitted.

1.7 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
 - 1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
 - 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:
 - 1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
 - 2. Keynoting: Materials and products are identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

BLANK PAGE

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

1.2 MINOR CHANGES IN THE WORK

A. Engineer will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Supplemental Instructions."

1.3 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Engineer will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 - e. Quotation Form: Use forms acceptable to Architect.
- B. Contractor-Initiated Work Change Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Engineer.
 - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.

- 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
- 4. Include costs of labor and supervision directly attributable to the change.
- 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- 6. Comply with requirements in Division 01 Section "Substitution Procedures" if the proposed change requires substitution of one product or system specified.
- 7. Work Change Proposal Request Form: Use form acceptable to Engineer.

1.4 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Changes Proposal Request, Engineer will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

1.5 CONSTRUCTION CHANGE DIRECTIVE

- A. Work Change Directive: Engineer may issue a Work Change Directive on AIA Document G714. Work Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 - 1. Work Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Work Change Directive.
 - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Requirements:
 - 1. Division 01 Section "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
 - 2. Division 01 Section "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.2 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule. Cost-loaded Critical Path Method Schedule may serve to satisfy requirements for the schedule of values.
 - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with continuation sheets.
 - b. Submittal schedule.
 - Items required to be indicated as separate activities in Contractor's construction schedule.
 - 2. Submit the schedule of values to Engineer at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
 - 3. Subschedules for Phased Work: Where the Work is separated into phases requiring separately phased payments, provide subschedules showing values coordinated with each phase of payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Name of Engineer.
 - c. Engineer's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 - 2. Arrange schedule of values consistent with format of AIA Document G703.
 - 3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project
 - 4. Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
 - 5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
 - 6. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.

OGDEN SCHOOL DISTRICT MOUND FORT MIDDLE SCHOOL

STAGE LIGHTING CONTROLS UPGRADE SEPTEMBER 2023

- 7. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
- 8. Allowances: Provide a separate line item in the schedule of values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.
- 9. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
 - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the schedule of values or distributed as general overhead expense, at Contractor's option.
- 10. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.3 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Engineer and paid for by Owner.
 - 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment, or as provide by the owner.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Engineer will return incomplete applications without action.
 - 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 - 2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
- E. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Engineer by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
 - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- F. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 - 1. List of subcontractors.
 - 2. Schedule of values.
 - 3. Contractor's construction schedule (preliminary if not final).
 - 4. Submittal schedule (preliminary if not final).
 - List of Contractor's staff assignments.
 - 6. List of Contractor's principal consultants.
 - 7. Copies of building permits.
 - 8. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 - 9. Initial progress report.

STAGE LIGHTING CONTROLS UPGRADE SEPTEMBER 2023

- 10. Report of preconstruction conference.
- 11. Certificates of insurance and insurance policies.
- G. Application for Payment at Substantial Completion: After Engineer issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
 - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 - 2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- H. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
 - 1. Evidence of completion of Project closeout requirements.
 - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 - 3. Updated final statement, accounting for final changes to the Contract Sum.
 - 4. AIA Document G706-1994, "Contractor's Affidavit of Payment of Debts and Claims."
 - 5. AIA Document G706A-1994, "Contractor's Affidavit of Release of Liens."
 - 6. AIA Document G707-1994, "Consent of Surety to Final Payment."
 - 7. Evidence that claims have been settled.
 - 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
 - 9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

BLANK PAGE

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.

B. Related Requirements:

- Division 01 Section "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
- 2. Division 01 Section "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.2 DEFINITIONS

 A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action.

1.3 ACTION SUBMITTALS

A. Submittal Schedule: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Engineer and additional time for handling and reviewing submittals required by those corrections.

1.4 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Engineer's Digital Data Files: Electronic copies of digital data files of the Contract Drawings will not be provided by Architect for Contractor's use in preparing submittals.
 - 1. Engineer will NOT furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings.
 - Engineer makes no representations as to the accuracy or completeness of digital data drawing files as they relate to the Contract Drawings.
 - b. Contractor shall execute a data licensing agreement in the form of AIA Document C106, Digital Data Licensing Agreement.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.

1.5

Coordinate transmittal of different types of submittals for related parts of the Work so
processing will not be delayed because of need to review submittals concurrently for
coordination.

STAGE LIGHTING CONTROLS UPGRADE SEPTEMBER 2023

- a. Engineer reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- B. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Engineer's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 - 3. Resubmittal Review: Allow 15 days for review of each resubmittal.
- C. Paper Submittals: Place a permanent label or title block on each submittal item for identification.
 - Indicate name of firm or entity that prepared each submittal on label or title block.
 - 2. Provide a space approximately 6 by 8 inches on label or beside title block to record Contractor's review and approval markings and action taken by Engineer.
 - 3. Include the following information for processing and recording action taken:
 - a. Project name.
 - b. Date.
 - c. Name of Engineer.
 - d. Name of Contractor.
 - e. Name of subcontractor.
 - f. Name of supplier.
 - g. Name of manufacturer.
 - h. Submittal number or other unique identifier, including revision identifier.
 - 1) Submittal number shall use Specification Section number followed by a decimal point and then a sequential number (e.g., 061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., 061000.01.A).
 - i. Number and title of appropriate Specification Section.
 - j. Drawing number and detail references, as appropriate.
 - k. Location(s) where product is to be installed, as appropriate.
 - Other necessary identification.
 - 4. Additional Paper Copies: Unless additional copies are required for final submittal, and unless Engineer observes noncompliance with provisions in the Contract Documents, initial submittal may serve as final submittal.
 - a. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Engineer.
- 1.6
- 1. Transmittal for Paper Submittals: Assemble each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Engineer will discard submittals received from sources other than Contractor.
 - a. Transmittal Form for Paper Submittals: Use AIA Document G810.
 - b. Transmittal Form for Paper Submittals: Provide locations on form for the following information:
 - 1) Project name.
 - 2) Date.
 - 3) Destination (To:).
 - 4) Source (From:).
 - 5) Name and address of Engineer.
 - 6) Name of Contractor.
 - 7) Name of firm or entity that prepared submittal.

OGDEN SCHOOL DISTRICT MOUND FORT MIDDLE SCHOOL

STAGE LIGHTING CONTROLS UPGRADE SEPTEMBER 2023

- 8) Names of subcontractor, manufacturer, and supplier.
- 9) Category and type of submittal.
- 10) Submittal purpose and description.
- 11) Specification Section number and title.
- 12) Specification paragraph number or drawing designation and generic name for each of multiple items.
- 13) Drawing number and detail references, as appropriate.
- 14) Indication of full or partial submittal.
- 15) Transmittal number.
- 16) Submittal and transmittal distribution record.
- 17) Remarks.
- 18) Signature of transmitter.
- B. Options: Identify options requiring selection by Engineer.
- C. Deviations: Identify deviations from the Contract Documents on submittals.
- D. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
 - 1. Note date and content of previous submittal.
 - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 - 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- E. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- F. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Engineer's action stamp.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements:
 - Action Submittals: Submit three paper copies of each submittal unless otherwise indicated. Architect will return two copies.
 - 2. Informational Submittals: Submit two paper copies of each submittal unless otherwise indicated. Engineer will not return copies.
 - Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
 - Provide a digital signature with digital certificate on electronically-submitted certificates and certifications where indicated.
 - b. Provide a notarized statement on original paper copy certificates and certifications where indicated.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
 - If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.

OGDEN SCHOOL DISTRICT MOUND FORT MIDDLE SCHOOL

STAGE LIGHTING CONTROLS UPGRADE SEPTEMBER 2023

- 2. Mark each copy of each submittal to show which products and options are applicable.
- 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.
 - g. Notation of coordination requirements.
 - h. Availability and delivery time information.
- 4. Submit Product Data before or concurrent with Samples.
- 5. Submit Product Data in the following format:
 - a. PDF electronic file.
 - b. Three paper copies of Product Data unless otherwise indicated. Engineer will return two copies.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
 - 1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Identification of products.
 - b. Schedules.
 - c. Compliance with specified standards.
 - d. Notation of coordination requirements.
 - e. Notation of dimensions established by field measurement.
 - f. Relationship and attachment to adjoining construction clearly indicated.
 - g. Seal and signature of professional engineer if specified.
 - 2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches, but no larger than 30 by 42 inches.
 - 3. Submit Shop Drawings in the following format:
 - a. PDF electronic file.
 - b. Three opaque copies of each submittal. Architect will retain two copies; remainder will be returned.
- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
 - 1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
 - 2. Identification: Attach label on unexposed side of Samples that includes the following:
 - a. Generic description of Sample.
 - b. Product name and name of manufacturer.
 - c. Sample source.
 - d. Number and title of applicable Specification Section.
 - 3. For projects where electronic submittals are required, provide corresponding electronic submittal of Sample transmittal, digital image file illustrating Sample characteristics, and identification information for record.
 - 4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
 - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.

STAGE LIGHTING CONTROLS UPGRADE SEPTEMBER 2023

- 5. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
 - a. Number of Samples: Submit three sets of Samples. Engineer will retain two Sample sets; remainder will be returned. Mark up and retain one returned Sample set as a project record sample.
 - 1) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least 3 sets of paired units that show approximate limits of variations.
- E. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
 - 1. Submit product schedule in the following format:
 - a. PDF electronic file.
- F. Coordination Drawings Submittals: Comply with requirements specified in Division 01 Section "Project Management and Coordination."
- G. Contractor's Construction Schedule: Comply with requirements specified in Division 01 Section "Construction Progress Documentation."
- H. Application for Payment and Schedule of Values: Comply with requirements specified in Division 01 Section "Payment Procedures."
- Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Division 01 Section "Closeout Procedures."
- J. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- K. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
- L. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
- M. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
- N. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.

2.2 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
 - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Engineer.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF electronic file and three paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
 - Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Engineer.
- B. Project Closeout and Maintenance Material Submittals: See requirements in Division 01 Section "Closeout Procedures."
- C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ENGINEER'S ACTION

- A. General: Engineer will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Engineer will review each submittal, make marks to indicate corrections or revisions required, and return it. Engineer will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.
- C. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- D. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

END OF SECTION 013300

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

B. Related Requirements:

1. Division 01 Section "Summary" for work restrictions and limitations on utility interruptions.

1.2 USE CHARGES

- A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Architect, testing agencies, and authorities having jurisdiction.
- B. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.
- C. Toilet Room: Use of Owner's existing designated toilet room is available for use. The contractor is required to maintain the toilet room in an acceptable clean condition, cleaning is required DAILY.

1.3 EQUIPMENT

A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

PART 2 - EXECUTION

2.1 TEMPORARY UTILITY

A. Electric Power Service: Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.

2.2 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
 - 1. Temporary field office space to be located within construction area.
 - 2. Maintain support facilities until Engineer schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial

Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

- B. Traffic Controls: Comply with requirements of authorities having jurisdiction.
 - 1. Protect existing site improvements to remain including curbs, pavement, and utilities.
 - 2. Maintain access for fire-fighting equipment and access to fire hydrants.
- C. Parking: Use designated areas (faculty area) of Owner's existing parking areas for construction personnel.

2.3 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Protection of Existing Facilities: Protect existing, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.
- B. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire prevention program.
 - 1. Prohibit smoking in construction areas.

2.4 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
 - 1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
 - At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Division 01 Section "Closeout Procedures."

END OF SECTION 015000

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

B. Related Requirements:

1. Division 01 Section "Substitution Procedures" for requests for substitutions.

1.2 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
 - Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a specific manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of additional manufacturers named in the specification.

1.3 ACTION SUBMITTALS

- A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Engineer's Action: If necessary, Engineer will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Engineer will notify Contractor of approval or rejection of proposed comparable product

request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

- a. Form of Approval: As specified in Division 01 Section "Submittal Procedures."
- b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Division 01 Section "Submittal Procedures." Show compliance with requirements.

1.4 QUALITY ASSURANCE

A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.

1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

- 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
- 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
- 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
- 4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.

C. Storage:

- 1. Store products to allow for inspection and measurement of quantity or counting of units.
- 2. Store materials in a manner that will not endanger Project structure.
- 3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
- Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
- 5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
- 6. Protect stored products from damage and liquids from freezing.

1.6 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
 - 1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
 - 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
 - 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 - 2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
 - 3. Refer to Divisions 02 through 33. Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Division 01 Section "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
 - 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 - 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 - 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
 - 4. Where products are accompanied by the term "as selected," Engineer will make selection.
 - 5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.

B. Product Selection Procedures:

- 1. Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
- 2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements.

Comparable products or substitutions for Contractor's convenience will not be considered.

Products:

- a. Restricted List: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
- b. Nonrestricted List: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product.

4. Manufacturers:

- a. Restricted List: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
- b. Nonrestricted List: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed, or a product by an unnamed manufacturer, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed manufacturer's product.
- 5. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
- C. Visual Matching Specification: Where Specifications require "match Engineer's sample", provide a product that complies with requirements and matches Engineer's sample. Engineer's decision will be final on whether a proposed product matches.
 - 1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Division 01 Section "Substitution Procedures" for proposal of product.
- D. Visual Selection Specification: Where Specifications include the phrase "as selected by Engineer from manufacturer's full range" or similar phrase, select a product that complies with requirements. Engineer will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:
 - 1. Construction layout.
 - 2. Installation of the Work.
 - 3. Cutting and patching.
 - 4. Progress cleaning.
 - 5. Protection of installed construction.
 - 6. Correction of the Work.

B. Related Requirements:

- 1. Division 01 Section "Summary" for limits on use of Project site.
- 2. Division 01 Section "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, and final cleaning.

1.2 QUALITY ASSURANCE

- A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
 - 1. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.
 - 2. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Engineer's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
 - 1. For projects requiring compliance with sustainable design and construction practices and procedures, use products for patching that comply with requirements of Division 01 sustainable design requirements Section.

- B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
 - 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of inplace materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 - 1. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- B. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

3.3 CONSTRUCTION LAYOUT

A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks. If discrepancies are discovered, notify Engineer promptly.

3.4 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb and make horizontal work level.
 - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.

- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on site and placement in permanent locations.
- F. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- G. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- H. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.

3.5 CUTTING AND PATCHING

- A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 - 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.
- C. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- D. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.
- E. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.6 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
 - Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.

- 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F.
- 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
 - 1. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways.
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.

3.7 PROTECTION OF INSTALLED CONSTRUCTION

A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.

END OF SECTION 017300

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures.
 - 2. Final completion procedures.
 - 3. Warranties.
 - 4. Final cleaning.
 - 5. Repair of the Work.

B. Related Requirements:

1. Division 01 Section "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.2 ACTION SUBMITTALS

- A. Product Data: For cleaning agents.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Completion.

1.3 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Schedule of Maintenance Material Items: For maintenance material submittal items specified in other Sections.

1.5 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
- B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.

- 1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
- 2. Submit closeout submittals specified in individual Divisions 02 through 33 Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
- C. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
 - 1. Advise Owner of pending insurance changeover requirements.
 - 2. Complete final cleaning requirements, including touchup painting.
 - Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. Engineer will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Engineer, that must be completed or corrected before certificate will be issued.
 - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
 - 2. Results of completed inspection will form the basis of requirements for final completion.

1.6 FINAL COMPLETION PROCEDURES

- A. Preliminary Procedures: Before requesting final inspection for determining final completion, complete the following:
 - 1. Submit a final Application for Payment according to Division 01 Section "Payment Procedures."
 - 2. Certified List of Incomplete Items: Submit certified copy of Engineer's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Engineer. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
 - 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
- B. Inspection: Submit a written request for final inspection to determine acceptance. On receipt of request, Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. Engineer will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
 - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.7 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
 - 1. Organize list of spaces in sequential order.
 - 2. Submit list of incomplete items in the following format:
 - a. Three paper copies unless otherwise indicated. Engineer will return two copies.

1.8 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
 - 1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
 - 2. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
- C. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.
 - 1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

PART 3 - EXECUTION

3.1 FINAL CLEANING

A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.

- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
 - b. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean according to manufacturer's recommendations if visible soil or stains remain.
 - c. Leave Project clean and ready for occupancy.

3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair or remove and replace defective construction. Refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged items cannot be repaired or restored, provide replacements.

ELECTRICAL GENERAL PROVISIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Architectural, Structural, Mechanical and other applicable documents are considered a part of the electrical documents insofar as they apply as if referred to in full. Contractor must review the entire set of plans and specifications. Reviewing only the electrical set is not acceptable.

1.2 DESCRIPTION OF WORK:

A. The extent of electrical work is indicated on drawings and/or specified in Divisions 26 sections of the specification. Provide all labor, materials, equipment, supervision and service necessary for a complete electrical system. Work includes, but is not necessarily limited to, the following items.

	<u>ITEM</u>	<u>SECTION</u>
1.	Electrical General Provisions	26 0500
2.	Electrical Submittals and Spare Parts	26 0502
3.	Electrical Connections for Equipment	26 0507
4.	Conductors and Cables	26 0519
5.	Grounding	26 0526
6.	Supporting Devices	26 0529
7.	Conduit Raceway	26 0532
8.	Electrical Boxes and Fittings	26 0533
9.	Electrical Seismic Control	26 0548
10.	Electrical Identification	26 0553
11.	Wiring Devices	26 2726
12.	Overcurrent Protective Devices	26 2815
13.	Demolition	26 4119
14.	Stage Lighting and Dimming System	26 5561

- B. Use of standard industry symbols together with the special symbols, notes, and instructions indicated on the drawings describe the work, materials, apparatus and systems required as a portion of this work.
- C. Visit the site during the bidding period to determine existing conditions affecting electrical and other work. All costs arising from site conditions and/or preparation shall be included in the base bid. No additional charges will be allowed due to inadequate site inspection.

1.3 DEFINITION OF TERMS

- A. The following terms used in Divisions 26 documents are defined as follows:
 - 1. "Provide": Means furnish, install and connect, unless otherwise indicated.
 - 2. "Furnish": Means purchase and deliver to project site.
 - 3. "Install": Means to physically install the items in-place.
 - 4. "Connect": Means make final electrical connections for a complete operating piece of equipment.

1.4 RELATED SECTIONS:

- A. Consult all other sections, determine the extent and character of related work and properly coordinate work specified herein with that specified elsewhere to produce a complete installation.
- B. General and Supplementary Conditions: Drawings and general provisions of contract and Division 1 of the Specifications, apply to all Division 26, 27 and 28 sections.

C. Painting:

1. Provide surface preparation, priming and finish coating as required for electrical cabinets, exposed conduit, pull and junction boxes, poles, surface metal raceways, etc. See Division 9, Finishes for material and installation requirements.

1.5 INTERPRETATION OF DRAWINGS AND SPECIFICATIONS:

A. Before bidding, Contractor shall familiarize himself with the drawings, specifications and project site. Submit requests for clarification to Architect/Engineer in writing prior to issuance of final addendum. After signing the contract, the Contractor shall meet the intent, purpose, and function of the Contract Documents. Any costs of materials, labor and equipment arising therefrom, to make each system complete and operable, is the responsibility of the Contractor.

1.6 REQUESTS FOR INFORMATION (RFIs):

- A. Contractor shall review all Contract Documents thoroughly before submitting an RFI to avoid unnecessary questions and ensure the question has not already been addressed within the existing Contract Documents.
- B. RFIs should be used to seek clarification on issues or areas of confusion that cannot be resolved through a review of the Contract Documents.
- C. Each RFI shall contain the following:
 - 1. Description of the Issue/Question: Clearly detail the issue or confusion, referencing the related Contract Document drawings and/or specifications.
 - Relevant Documents: Attach any necessary supporting documents that could aid in understanding the RFI.
 - 3. Proposed Solution: Suggest a possible resolution to the problem or confusion.

D. Non-Compliant RFIs

 Frivolous or incomplete RFIs will not be accepted. RFIs that do not follow the guidelines set forth in this section, or are deemed unnecessary, may be returned without response at the discretion of the Engineer.

1.7 QUALITY ASSURANCE:

- A. Reference to codes, standards, specifications and recommendations of technical societies, trade organizations and governmental agencies refers to the latest edition of such publications adopted and published prior to submittal of the bid proposed, unless noted otherwise herein. Such codes or standards are considered a part of this specification as though fully repeated herein.
- B. When codes, standards, regulations, etc. allow work of lesser quality or extent than is specified under this Division, nothing in said codes shall be construed or inferred as reducing the quality, requirements or extent of the Drawings and Specifications. Perform

work in accordance with applicable requirements of all governing codes, rules and regulations including the following minimum standards, whether statutory or not:

- 1. National Electric Code (NEC).
- 2. International Building Code (IBC).
- 3. International Fire Code (IFC).
- 4. International Mechanical Code (IMC).
- C. Standards: Comply with the following standards where applicable for equipment and materials specified under this Division.

1.	UL	Underwriters' Laboratories
2.	ASTM	American Society for Testing Materials
3.	CBN	Certified Ballast Manufacturers
4.	IPCEA	Insulated Power Cable Engineers Association
5.	NEMA	National Electrical Manufacturer's Association
6.	ANSI	American National Standards Institute
7.	ETL	Electrical Testing Laboratories

- D. All electrical apparatus furnished under this Section shall conform to (NEMA) standards and the NEC and bear the Underwriters' Laboratories (UL) label where such label is applicable.
- E. Comply with requirements of State and Local Ordinances. If a conflict occurs between these requirements and the Contract Documents, the most stringent requirements shall govern. The Contractor accepts this responsibility upon submitting his bid, and no extra charge will be allowed after the contract is awarded. This shall not be construed as relieving the Contractor from complying with any requirements of the Contract Documents that may be in excess of the aforementioned requirements, and not contrary to same.
- F. Obtain all permits, inspections, etc. required by authority having jurisdiction. Include all fees in bid. Furnish a certificate of approval to the Owner's Representative from the Inspection Authority at completion of the work.
- Employ only qualified craftsmen with at least three years of experience. Workmanship shall be neat, have a good mechanical appearance and conform to best electrical construction practices. Provide a competent superintendent to direct the work at all times. Any person found incompetent shall be discharged from the project and replaced by satisfactory personnel.
- Н. Contractor shall have a current state contracting license applicable to type of work to be performed under this contract.
- I. Required Pre-Electrical Construction Meeting with Electrical Engineer: Electrical contractor/representative will be required to attend a pre-electrical construction meeting (approximately 30-60 minutes) with engineering representative in the electrical engineers office prior to electrical construction commencement. This meeting will address any questions on the part of the contractor and the expectations of the Engineer with regard to specifications, plans and site visits for both rough and finish electrical work.

CONSTRUCTION CHANGE ORDER PROPOSALS 1.8

- A. In the event that a submission of a change order is issued by the contractor, the following information will be required to be submitted by the contractor, prior to any consideration by the owner/architect.
 - Where project manager or project engineer work is required, the labor cost a. shall not exceed 2% of the electrical portion of the change order.
 - b. All equipment, including conduit and wire, shall be itemized, identifying unit costs and quantities of equipment. Distributor quotes shall accompany all change order requests. The distributor quotes shall include costs for all

- equipment including conduit and wire. Lot pricing for equipment is not acceptable.
- c. The general contractor shall review and confirm that the quantity and costs of materials submitted appear reasonable for the scope proposed.
- d. Labor units shall not exceed base NECA #1 standards. No adjustment factors shall be approved.
- e. Any research and labeling time, shall be the responsibility of the electrical contractor and shall not be included in the change order request.
- f. Any costs associated with the purchase of tools or transportation shall be fully itemized for review by architect/owner.
- g. Overtime rates shall only be approved where additional manpower cannot achieve the same result.
- h. Change order form shall follow the following format:
 - i. PCO number
 - ii. Detailed description of work being performed
 - iii. Location on project where work is performed
 - iv. Chosen NECA column
 - v. Identified material:
 - 1. QTY
 - 2. Unit cost
 - 3. Mark up
 - 4. Material total
 - vi. Identified labor:
 - 1. QTY
 - 2. Unit cost
 - 3. Composite labor rate
 - 4. Labor total

1.9 RECORD DRAWINGS:

- A. Contractor shall provide as-built drawings and a record model of the completed project, reflecting all deviations from the original design including but not limited to field conditions, RFIs, ASIs, and other modifications. The as-built drawings shall be provided in both Autodesk Revit and PDF formats.
- B. Maintain, on a daily basis, a complete set of "Record Drawings", reflecting an accurate record of work in accordance with the following:
 - 1. Show the complete routing and location of all feeders rated 100 amps and larger. Contractor shall clearly indicate dimensions on the drawings for work that is hidden beneath the ground or under slabs, concealed above ceiling structures, and within concealed spaces. These dimensions shall be measured from fixed structural elements, rather than from partition walls or other non-structural elements.
 - 2. Show the complete routing and location of all telecommunications conduits, systems raceways, and empty raceways, 1-1/4" and larger. Contractor shall clearly indicate dimensions on the drawings for work that is hidden beneath the ground or under slabs, concealed above ceiling structures, and within concealed spaces. These dimensions shall be measured from fixed structural elements, rather than from partition walls or other non-structural elements.
 - 3. Show all changes, deviations, addendum items, change orders, job instructions, etc., that change the work from that shown on the contract documents, including wall relocations, fixtures and device changes, branch circuiting changes, etc. Where locations of boxes, raceways, equipment, etc. are adjusted in the field to fit conditions, but such new locations may not be obvious by referring to the contract document, show new locations on the record drawings.
 - 4. Provide a copy of the raceway as-builts within the equipment rack for the system indicated below. Provide 11x17 size laminated prints that are legible.
 - a. Telecommunications

b. Audiovisual

- C. At the discretion of the Architect/Engineer, the drawings will be reviewed on a periodic basis and used as a pre-requisite for progress payments. This requirement shall not be construed as authorization for the Contractor to make changes in the layout, or work without written authorization for such changes.
- D. The Architect/Engineer shall review the drawings and the Contractor shall incorporate the resulting comments into the final record drawings.
- E. Certify the "Record Drawings" for correctness by placing and signing the following certifications of the first sheet of the drawings:

"CERTIFIED CORRECT (3/8" high letters)

(Name of General Contractor)	
Ву:	Date:
(Name of Electrical Contractor)	
Ву:	Date:

1.10 GUARANTEE:

A. Ensure that electrical system installed under this contract is in proper working order and in compliance with drawings, specifications, and/or authorized changes. Without additional charge, replace any work or materials that develop defect, except from ordinary wear and tear, within one year from the date of substantial completion. Exception: Incandescent and fluorescent lamps shall be guaranteed for a period of two months from the date of substantial completion.

1.11 OTHER:

A. Right to Hire. "Client" agrees that during the project and for a period of twenty four (24) months following substantial completion that it will not, directly or indirectly, employ or solicit to employ BNA Personnel.

PART 2 - PRODUCTS

2.1 GENERAL:

A. Products are specified by manufacturer name, description, and/or catalog number. Discrepancies between equipment specified and the intended function of equipment shall be brought to the attention of the Architect/Engineer in writing prior to bidding. Failure to report any conflict, including catalog numbers, discontinued products, etc., does not relieve the Contractor from meeting the intent of the contract documents nor shall it change the contract cost. If the Contractor is unable to interpret any part of the plans and/or specifications, or should he find discrepancies therein, he shall bring this to the attention of the Architect/Engineer who will issue interpretation and/or additional instructions to Bidders before the project is bid.

2.2 MANUFACTURERS:

A. Provide products of manufacturers specified. Manufacturers catalog numbers and descriptions establish the quality of product required. Substitutions will be considered if a duplicate written application (2-copies) is at the office of the Architect/Engineer eight (8) working days prior to the day of the bidding. The application shall include the following: 1)

A statement certifying that the equipment proposed is equal to that specified; that it has the same electrical and physical characteristics, compatible dimensions, and meets the functional intent of the contract documents; 2) The specified and submittal catalog numbers of the equipment under consideration; 3) A pictorial and specification brochure.

- B. Any conflict arising from the use of substituted equipment shall be the responsibility of the Contractor, who shall bear all costs required to make the equipment comply with the intent of the contract documents.
- C. Samples may be required for non-standard or substituted items before installation during construction. Provide all samples as required.
- D. No materials or apparatus may be substituted after the bid opening except where the equipment specified has been discontinued.
- E. Provide only equipment specified in the Contract Documents or approved by addendum.

2.3 SPARE PARTS:

A. Provide spare parts (fuses, diffusers, lamps, etc.) as specified. Transmit all spare parts to Owner's Representative prior to substantial completion.

PART 3 - EXECUTION

3.1 INSTALLATION:

- A. Layout electrical work in advance of construction to eliminate unnecessary cutting, drilling, channeling, etc. Where such cutting, drilling, or channeling becomes necessary for proper installation; perform with care. Use skilled mechanics of the trades involved. Repair damage to building and equipment at no additional cost to the contract. Cutting work of other Contractors shall be done only with the consent of that Contractor. Cutting structural members shall not be permitted.
- B. Provide equipment enclosures appropriate to the environment to which they are installed. For example, provide NEMA 3R for exterior enclosures and NEMA 1 for interior enclosures unless otherwise noted.
- C. Since the drawings of floor, wall, and ceiling installation are made at small scale; outlets, devices, equipment, etc., are indicated only in their approximate location unless dimensioned. Locate outlets and apparatus symmetrically on floors, walls and ceilings where not dimensioned, and coordinate such locations with work of other trades to prevent interferences. Verify all dimensions on the job. Do not scale the electrical drawings, but refer to the architectural and mechanical shop drawings and project drawings for dimensions as applicable.
- D. Perform for other trades, the electrical wiring and connection for all devices, equipment or apparatus. Consult Architectural, Mechanical, and other applicable drawings, and all applicable shop drawings to avoid switches, outlets, and other equipment from being hidden behind doors, cabinets, counters, heating equipment, etc., or from being located in chalkboards, tackboards, glass panels, etc. Relocate buried electrical devices and/or connections as directed at no additional cost.
- E. Coordinate the location of outlets, devices, connections, and equipment with the supplier of the systems furniture prior to rough-in.
- F. Where conduit, outlets or apparatus are to be encased in concrete, it must be located and secured by a journeyman or foreman present at the point of installation. Check locations of the electrical items before and after concrete and/or masonry installation and relocate displaced items.
- G. Provide block-outs, sleeves, demolition work, etc., required for installation of work specified in this division.

3.2 CLEAN:

- A. Clean up all equipment, conduit, fittings, packing cartons and other debris that is a direct result of the installation of the work of this Division.
- B. Clean fixtures, interiors and exteriors of all equipment, and raceways. Replace all filters in electrical equipment upon request for Substantial Completion.

3.3 POWER OUTAGES:

- A. All power outages required for execution of this work shall occur during non-standard working hours and at the convenience of the Owner. Include all costs for overtime work in bid.
- B. Submit written request at least 7 days in advance of scheduled outage and proceed with outage only after receiving authorization from the Owner's Representative.
- C. Keep all outages to an absolute minimum.

3.4 STORAGE AND PROTECTION OF MATERIALS:

A. Provide storage space for storage of materials and apparatus and assume complete responsibility for all losses due to any cause whatsoever. In no case shall storage interfere with traffic conditions in any public thoroughfare or constitute a hazard to persons in the vicinity. Protect completed work, work underway, and apparatus against loss or damage.

3.5 FIRE PENETRATION SEALS:

A. Seal all penetrations for work of this section through fire rated floors, walls and ceilings to prevent the spread of smoke, fire, toxic gas or water through the penetration either before, during or after fire. The fire rating of the penetration seal shall be at least that of the floor, wall or ceiling that it is installed, so that the original fire rating of the floor or wall is maintained as required by Article 300-21 of the National Electrical Code. Where applicable, provide OZ Type CFSF/I and CAFSF/I fire seal fittings for conduit and cable penetrations through concrete and masonry walls, floors, slabs, and similar structures. Where applicable, provide 3M CID cast-in device for floor slabs. Where applicable, provide 3M fire barrier sealing penetration system, and/or IPC Flame Safe Fire Stop System, and/or Chase Foam fire stop system, including wall wrap, partitions, caps, and other accessories as required. All materials to comply with UL 1479 (ASTM E-814). Comply with manufacturer's instructions and recommendations for installation of sealing fittings and barrier sealing systems.

3.6 PROJECT FINALIZATION AND START-UP:

- A. Upon completion of equipment and system installation, assemble all equipment Factory Representatives and Subcontractors for system start-up.
- B. Each Representative and Subcontractor shall assist in start-up and check out their respective system and remain at the site until the total system operation is accepted by the Owner's representative.
- C. The Factory Representative and/or System Subcontractor shall give personal instruction on operating and maintenance of their equipment to the Owner's maintenance and/or operation personnel. To certify acceptance of operation and instruction by the Owner's Representative, the contractor shall prepare a written statement as follows:
 - This is to certify that the Factory Representative and System Subcontractor for each of the systems listed below have performed start-up and final check out of their respective systems.
 - 2. The Owner's Representative has received complete and thorough instruction in the operation and maintenance of each system.

STAGE LIGHTING CONTROLS UPGRADE SEPTEMBER 2023

	SYSTEM (List systems included)	FACTORY REPRESENTATIVE (List name and address of Factory Representative)
	Owner's Representative	Contractor
D.	Send copy of acceptance to A	rchitect/Engineer.

3.7 FINAL REVIEW:

A. At the time of final review, the project foreman shall accompany the reviewing party, and remove coverplates, panel covers and other access panels as requested, to allow review of the entire electrical system.

ELECTRICAL SUBMITTALS, O & M MANUALS AND SPARE PARTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to all Division 26 sections.
- B. Consult all other sections, determine the extent and character of related work and properly coordinate work specified herein with that specified elsewhere to produce a complete installation.

1.2 SUBMITTAL REQUIREMENTS:

A. GENERAL:

- 1. After the Contract is awarded but prior to ordering, manufacture, or installation of any equipment, prepare complete Submittals including shop drawings, product data, brochures, etc. for materials and equipment as required by each section of the specification.
- Review of Submittals shall not relieve the Contractor of responsibility for dimensions and/or errors that may be contained therein, or deviations from the Contract Document's requirements. It shall be clearly understood that the noting of some errors but overlooking others does not grant the Contractor permission to proceed in error. Regardless of any information contained in the Shop Drawings and Brochures, the requirements of the Contract Document's shall govern and are not waived, or superseded in any way by the review of the Shop Drawings and Brochures.
- Submittals are reviewed, not approved. Comments made within submittals do not alter the contract documents in any way. The contractor is still responsible, regardless of comments (if any) made within submittals, for complying with drawings and specifications.
- 4. Notify engineer in writing if any of the comments noted in the submittals alter the contract cost. A comment within the submittal process which increases/decreases cost of product is not an authorization to the contractor under any circumstances to proceed.
- 5. Notify engineer of any modifications between contract documents and submittals. It is the responsibility of the contractor to ensure compliance.
- 6. ELECTRONIC SUBMITTAL REQUIREMENTS:
 - a. Provide submittals in Portable Document Format (PDF).
 - b. Documents must be electronically bookmarked by Division e.g. 26, 27 and 28, Specification section e.g. 26 0510 and individually for each item submitted for light fixtures, switchgear, transformer, panelboard etc. and keyword searchable using Adobe Acrobat (http://www.adobe.com/acrobat) or Bluebeam Revu (http://www.bluebeam.com) for each relevant section.
 - c. Electronically highlight <u>all options</u> for light fixtures, electrical equipment, etc. Manual highlighting and scanning of the documents is NOT acceptable and will NOT be reviewed.
 - d. Provide only completed cutsheets for all fixture and equipment types. Blank cutsheets submitted with a schedule are NOT acceptable and will NOT be reviewed.

- e. At the time of submission, the electrical contractor shall provide a complete and comprehensive submission of all required specification sections/shop drawings at the same time. Exceptions may be given, with prior approval, for time-sensitive equipment.
- f. A maximum of one submittal per specification section is allowed. It is NOT acceptable to provide a product by product submittal. Single product by product submittals will NOT be reviewed.

B. SCHEDULING

GENERAL

- a. A minimum period of two weeks, exclusive of transmittal time, will be required each time Submittals are submitted or resubmitted for review. This time period shall be considered by the Contractor when scheduling submittal data.
- b. If the shop drawings are rejected twice, the contractor shall reimburse the engineering firm the sum of \$1,200.00 for the third review and any additional reviews required prior to the commencement of additional review.

C. QUALITY ASSURANCE

PRE-SUBMITTAL PREPARATION

- a. Prior to submission of the Shop Drawings and Project Data, review and certify that they are in compliance with the Contract Documents. Verify all dimensional information to ensure proper clearance for installation of equipment.
- b. Shop drawings requiring the use of electronic documents (floor plans, Lighting plans, fire alarm plans, etc.) shall be requested via a request for information (RFI) through the general contractor. Electronic documents will be provided to the Architect for distribution. No direct vendor requests will be accepted.
- c. Contractor is completely responsible for the content of the submittal

2. SUBMITTAL REQUIREMENTS

- a. Provide a stamp or statement on each submittal as follows:
 - I hereby certify that this Shop Drawing and/or Brochure has been checked prior to submittal and that it complies in all respects with the requirements of the Contract Drawings and Specifications for this Project.

(Name of Electrical Subcontractor)

Name		
Position	Date	

- i. Failure to provide certification will result in submittals being rejected and returned without review.
- b. Brochures to be submitted as supplementary information shall be published by the Manufacturers and shall contain complete and detailed engineering and dimensional information. Brochures submitted shall contain only information relevant to the particular equipment or materials to be furnished. The Contractor shall not submit catalogs that describe several different items in addition to those items to be used, unless all irrelevant information is marked out, or unless relevant information is clearly marked. Brochures from each manufacturer shall be identified and submitted separately.

- c. Shop Drawings shall be done in an easily legible scale and shall contain sufficient plans, elevations, sections, and isometrics to clearly describe the equipment or apparatus, and its location. Drawings shall be prepared by an Engineer/Draftsmen skilled in this type of work. Shop Drawings shall be drawn to at least 1/4" = 1'0" scale.
- d. Observe the following rules when submitting the Shop Drawings and Brochures.
 - Each Shop Drawing shall indicate in the lower right hand corner, and each Brochure shall indicate on the front cover the following: Title of the sheet or brochure, name and location of the building; names of the Architect and Electrical Engineer, Contractor, Subcontractors, Manufacturer, Supplier/Vendor, etc., date of submittal, and the date of correction and revision. Unless the above information is included the submittal will be rejected and returned without being reviewed.
 - Submittal Identification shall include the following:
 - a. A unique number, sequentially assigned, shall be noted on the transmittal form accompanying each item submitted.
 - b. Original submittal numbers shall have the following format: "XXX-Y;" where "XXX" is the originally assigned submittal number and "Y" is a sequential letter assigned for resubmittals (for example, A, B, or C being the first, second, and third resubmittals, respectively). Submittal 25B, for example, is the second resubmittal of Submittal 25.

D. POST-SUBMITTAL

1. Check all materials and equipment after arrival on the job site and verify compliance with the Contract Documents.

1.3 PROVIDE SUBMITTALS AS REQUESTED FOR EACH OF THE SECTIONS LISTED BELOW:

A. 26 0519 Conductors and Cables

i.

- 1. (600V and Below)
 - a. Submit megohmmeter test data for circuits under 600 volts. Megger all circuits of 100 amp and greater rating.
- 2. Conductors and Cables (Medium and Low Voltage)
 - a. Submit manufacturer's data on electrical cable and connectors for use above 600 volts. Upon request of Architect/Engineer, submit certificate of compliance indicating that cable has been tested in accordance with ICEA S-68-516, AE16 #6 and UL Standard 1072, and meets or exceeds minimum requirements.
 - b. Submit test data in accordance with IEEE Standard 400-2001 showing ambient conditions, voltage levels, level durations, and conduction current for each step. Include effective insulation resistance in submittal.
 - c. Submit medium voltage cable Splicer/Terminator certification of

competency and experience 20 days before splices or terminations are made in medium voltage cables. Splicer/Terminator experience during the immediate past 3 years shall include performance in splicing and terminating cables of the type and classification being provided under this contract.

B. 26 0526 Grounding

- Submit the name of test agency to be used for testing specified in this section. Submit results of tests specified in this section. Also include test results in Operation and Maintenance Manuals as specified.
- C. 26 0532 Conduit Raceway
 - 1. Submit manufacturer's data on MC-PCS Power & Control/Signal Cable.
- D. 26 0533 Electrical Boxes and Fittings
 - 1. Submit manufacturer's data including specifications, installation instruction and general recommendations for each type of floor box used on project.
- E. 26 0548 Electrical Seismic Control
 - A single submittal shall be provided for all seismic anchorage and restraints for all Division 26 equipment and systems provided as part of this project. Individual submittals for specific systems will not be accepted.
 - 2. Submit shop drawings, calculations, and printed data for the following items under provisions of the General Conditions of the Contract:
 - a. Complete engineering calculations and shop drawings for all seismic requirements for all equipment to be restrained as outlined in Section 26 0548 Specification, and as detailed on drawings.
 - b. The professional seal of the engineer who is responsible for the design of the Seismic Restraint System.
 - c. Details for all seismic bracing.
 - d. Details for steel frames, concrete inertia bases, and housekeeping pads. Include dimensions, embed depths, dowelling details, and concrete reinforcing requirements.
 - e. Clearly outlined procedures for installing and adjusting the isolators, seismic bracing anchors, snubbers, cables, and bolt connections.
 - f. Floor plan noting the locations, size, and type of anchorage and restraint to be used.
 - g. Include confirmation that all calculations are based on the design criteria listed in appropriate Section.
 - h. Certificate of Compliance.
 - i. Where equipment is exempt per this specification provide a written certificate of compliance for each of the systems noted with the professional seal of engineer who has reviewed the electrical system.
- F. 26 0553 Electrical Identification
 - 1. Submit manufacturer's data on each type of electrical identification products
 - a. Submit one sample of each component of the electrical identification system as follows: Wire/cable tape marker, Tags, Engraved, plastic laminate labels, Arc-flash hazard labels
- G. 26 2726 Wiring Devices

1. Submit manufacturer's data on electrical wiring devices.

H. 26 2815 Overcurrent Protective Devices

- Submit manufacturer's data and shop drawings only after completion of the preliminary protective device study (see Section 26 0573 as applicable). Any Section 26 2815 submittals received prior to submission of the preliminary protective device study will be REJECTED.
- 2. Submit manufacturer's data on overcurrent protective devices, including catalog cuts, time-current trip characteristic curves, and mounting requirements.
- 3. Submit layout drawings of overcurrent protective devices, with layouts of circuit breakers, including spatial relationships to proximate equipment. Failure to submit said spatial layouts does not relieve contractor of responsibility to verify all required clearances before release of equipment for fabrication.
- 4. Submit time-current trip curves (in log-log format) and trip setting parameter/range information (for each trip function) for all solid-state circuit breakers.
- 5. Manufacturer shall also provide recommended trip settings with the shop drawing submittal (including ground fault settings) for coordination with downstream overcurrent devices. Manufacturer shall base recommendations on the AIC rating of the electrical equipment.
- 6. Where the Protective Device Study specification section 260573 is included in the project, the time-current curves and recommended trip settings for all solid-state circuit breakers shall be submitted as part of the protective device study.

I. 26 5561 Stage Lighting and Dimming System

- 1. Submit manufacturer's data on stage lighting and dimming systems, including, but not limited to, dimmer racks, control consoles, lighting instruments, connector strips, receptacles, instructions for installation, operation and maintenance, suitable for inclusion in maintenance manuals.
- 2. Submit dimensioned drawings of stage lighting and dimming system components and accessories. Show accurately scaled layouts of system components. Provide wiring diagrams for inter connection of system components.

1.4 OPERATION & MAINTENANCE MANUALS

- A. Provide operating instruction and maintenance data books for all equipment and materials furnished under this Division.
- B. Submit four copies of operating and maintenance data books for review at least four weeks before final review of the project. Assemble all data in a completely indexed volume or volumes and identify the size, model, and features indicated for each item. The binder (sized to the material) shall be a 2" slide lock unit (Wilson-Jones WLJ36544B). The cover shall be engraved with the job title in 1/2" high letters and the name and address of the Contractor in 1/4" high letters. Provide the same information in 1/8" letters on the spine.
- C. Include complete cleaning and servicing data compiled in clearly and easily understandable form. Show serial numbers of each piece of equipment, complete lists of replacement parts, motor ratings, etc. Each unit shall have its own individual sheet. (Example: If two items of equipment A and D appear on the same sheet, an individual sheet shall be provided for each unit specified).
- D. Include the following information where applicable.
 - 1. Identifying name and mark number.
 - 2. Certified outline Drawings and Shop Drawings.
 - Parts lists.
 - 4. Performance curves and data.

- 5. Wiring diagrams.
- Light fixture schedule with the lamps and ballast data used on the project for all fixtures
- 7. Manufacturer's recommended operating and maintenance instructions.
- 8. Vendor's name and address for each item.
- E. The engineer shall review the manuals and when approved, will forward the manuals on to the architect. If the manuals are rejected twice, the contractor shall reimburse the engineer the sum of \$1,200.00 for each review afterwards.
- F. Provide Operation and Maintenance Manual information for each section listed below in addition to the general requirements listed above.
 - 1. 26 0526 Grounding
 - a. Test Results of measured resistance values
 - 2. 26 0548 Electrical Seismic Control
 - a. Certificate of Compliance from Final Inspection

1.5 SPARE PARTS:

- A. Provide spare parts (fuses, diffusers, lamps, etc.) as specified. Stock of all spare items shall be delivered as directed to Owner's storage space prior to substantial completion. All components shall be labeled to match construction document nomenclature.
- B. Review with Owner/Architect and revise as needed for each project.

Section	Section Name	Description	Qty. Required	Qty. Received	Fulfilled?
26 0532	Conduit Raceway Provide 1000 feet of ¾" conduit with 3 #12 conductors and 1000 feet of ¾" conduit with 3 #10 conductors. Provide all supports, fittings, boxes, terminations, etc. as required for installation. Install only as directed by engineer. Credit back all unused material and labor to Owner.		Per description		
26 2815	Overcurrent Protective Devices	For types and ratings required, furnish additional fuses, amounting to one unit for every 5 installed units, but not less than two units of each size and type, unless specified otherwise in another section of these specifications.	Per description		

SECTION 260507

ELECTRICAL CONNECTIONS FOR EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section making reference to electrical connections.

1.2 DESCRIPTION OF WORK:

- A. Extent of electrical connection for equipment includes final electrical connection of all equipment having electrical requirements. Make final connections for all owner furnished equipment. See other applicable portions of specification for building temperature control wiring requirements.
- B. Refer to sections of other Divisions for specific individual equipment power requirements.

1.3 QUALITY ASSURANCE:

- A. NEC COMPLIANCE: Comply with applicable portions of NEC as to type products used and installation of electrical power connections.
- B. UL LABELS: Provide electrical connection products and materials that have been UL-listed and labeled.

PART 2 - PRODUCTS

2.1 GENERAL:

- A. For each electrical connection indicated, provide complete assembly of materials, including but not necessarily limited to, raceways, conductors, cords, cord caps, wiring devices, pressure connectors, terminals (lugs), electrical insulating tape, heat-shrinkable insulating tubing, cable ties, solderless wire nuts, and other items and accessories as needed to complete splices, terminations, and connections as required. Crimp on or slip-on type splicing materials (insulation displacement type) designed to be used without wire stripping are not acceptable. See Section 26 0532, Conduit Raceways; Section 26 2726 Wiring Devices: and Section 26 0519 Conductors and Cables for additional requirements. Provide final connections for equipment consistent with the following:
 - 1. Permanently installed fixed equipment flexible seal-tite conduit from branch circuit terminal equipment, or raceway; to equipment, control cabinet, terminal junction box or wiring terminals. Totally enclose all wiring in raceway.
 - 2. Movable and/or portable equipment wiring device, cord cap, and multi-conductor cord suitable for the equipment and in accordance with NEC requirements (Article 400).
 - 3. Other methods as required by the National Electrical Code and/or as required by special equipment or field conditions.

PART 3 - EXECUTION

3.1 INSTALLATION OF ELECTRICAL CONNECTIONS:

- A. Make electrical connections in accordance with connector manufacturer's written instructions and with recognized industry practices, and complying with requirements of NEC and NECA's "Standard of Installation" to ensure that products fulfill requirements.
- B. Connect electrical power supply conductors to equipment conductors in accordance with equipment manufacturer's written instructions and wiring diagrams.
- C. Coordinate installation of electrical connections for equipment with equipment installation work.
- D. Obtain and review the equipment shop drawings to determine particular final connection requirements before rough-in begins for each equipment item.
- E. Refer to basic materials and methods Section 26 0553 Electrical Identification, Conductors, for identification of electrical power supply conductor terminations.

CONDUCTORS AND CABLES (600V AND BELOW)

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to conductors and cables specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of electrical conductor and electrical cable work is indicated by drawings and schedules.
- B. Types of conductors and cables in this section include the following:
 - 1. Copper Conductors (600V)
- C. Applications for conductors and cables required for project include:
 - 1. Power Distribution
 - 2. Feeders
 - Branch Circuits
- **1.3 RECORDS SUBMITTAL:** Refer to Section 26 0502 for requirements.

1.4 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to construction and installation of electrical conductors and cable. Comply with UL standards and provide electrical conductors and cables that have been UL-listed and labeled.
- B. Comply with applicable portions of NEMA/Insulated Cable Engineers Association standards pertaining to materials, construction and testing of conductors and cable.
- C. Comply with applicable portions of ANSI/ASTM and IEEE standards pertaining to construction of conductors and cable.
- **1.5 SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS

2.1 COPPER CONDUCTORS (600V):

- A. Provide factory-fabricated conductors of sizes, ratings, materials, and types indicated for each service. Where not indicated provide proper selection to comply with project's installation requirements and NEC standards. Provide conductors in accordance with the following:
 - 1. Service Entrance Conductors –Copper conductor; see drawings for insulation type.
 - 2. Distribution and Panelboard Feeders; and Other Conductors, #2 AWG and Larger Copper conductor; see drawings for insulation type.
 - 3. Branch Circuit Conductors and All Conductors #3 AWG and Smaller Copper conductor, with THHN/THWN insulation. Size all conductors in accordance with

NEC; minimum size to be #12 AWG. Provide solid conductors for #10 AWG and smaller. Provide stranded conductors for #8 AWG and larger.

- B. Provide a maximum of three phase conductors in any one conduit or as approved by electrical engineer. Where phase conductors share a common neutral they must have a means to simultaneously disconnect all ungrounded conductors at the point where the branch circuits originate. The ungrounded and neutral conductors of a multi-wire branch circuit must be grouped together by wire ties at the point of origination. Provide one size larger neutral conductor than the branch circuit conductor for all multi-wire branch circuits.
- C. Provide neutral and ground wire as specified elsewhere in documents.
- D. Provide separate neutral conductor for all single phase branch circuits installed. No shared neutrals are allowed. Neutral conductor shall be the same size as the phase conductor.

PART 3 - EXECUTION

3.1 INSTALLATION:

- A. General: Install electric conductors and cables as indicated, in compliance with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standards of Installation", and in accordance with recognized industry practices.
- B. Coordinate installation work with electrical raceway and equipment installation work, as necessary for proper interface.
- C. Cables may be pulled by direct attachment to conductors or by use of basket weave pulling grip applied over cables. Attachment to pulling device shall be made through approved swivel connection. Nonmetallic jacketed cables of small size may be pulled directly by conductors by forming them into a loop that pull wires can be attached; remove insulation from conductors before forming the loop. Larger sizes of cable may be pulled by using basket weave pulling grip, provided the pulling force does not exceed limits recommended by manufacturer; if pulling more than one cable, bind them together with friction tape before applying the grip. For long pulls requiring heavy pulling force, use pulling eyes attached to conductors.
- D. Do not exceed manufacturer's recommendations for maximum allowable pulling tension, side wall pressure, and minimum allowable bending radius. In all cases, pulling tension applied to the conductors shall be limited to 0.008 lbs. per circular mil of conductor cross-section area.
- E. Pull in cable from the end having the sharpest bend; i.e. bend shall be closest to reel. Keep pulling tension to minimum by liberal use of lubricant, and turning of reel, and slack feeding of cable into duct entrance. Employ not less than one man at reel and one in pullhole during this operation.
- F. For training of cables, minimum bend radius to inner surface of cable shall be 12 times cable diameter.
- G. Where cable is pulled under tension over sheaves, conduit bends, or other curved surfaces, make minimum bend radius 50% greater than specified above for training.
- H. Use only wire and cable pulling compound recommended by the specific cable manufacturer, and that is listed by UL.
- I. Seal all cable ends unless splicing is to be done immediately. Conduit bodies shall not contain splices.
- J. Support all cables in pullholes, concrete trenches, and similar locations by cable racks and secure to rack insulators with nylon cord or self-locking nylon cable ties. Place each cable on separate insulator. In manholes, pullholes, concrete trenches, and similar locations, wrap strips of fire-proofing tape (approx. 1/16 inch thick by 3 inches wide) tightly around each cable spirally in half-lapped wrapping or in two butt-joined wrappings with the second

wrapping covering the joints in the first. Apply tape with the coated side toward the cable, and extend tape one inch into the ducts. To prevent unraveling, random wrap the fireproofing tape the entire length of the fireproofing with pressure sensitive glass cloth tape. Provide fireproofing tape of a flexible, conformable fabric having one side coated with flame retardant, flexible, polymeric coating and/or a chlorinated elastomer not less than 0.050 inch thick weighing not less than 2.5 pounds per square yard. Provide tape that is noncorrosive to cable sheath, self-extinguishing, and that will not support combustion. Construct tape of materials that do not deteriorate when subjected to oil, water, gases, salt water, sewage and fungus.

K. Follow manufacturer's instructions for splicing and cable terminations.

3.2 AFTER INSTALLATION TEST FOR CABLE 600 VOLTS AND BELOW:

- A. Prior to energization, test cable and wire for continuity of circuitry, and for short circuits, Megger all circuits of 100 amp and greater rating. Correct malfunctions. Record all test data and provide written test report.
- B. Subsequent to wire and cable connections, energize circuitry and demonstrate functioning in accordance with requirements.
- **3.3 IDENTIFICATION OF FEEDERS:** Refer to Section 26 0553 for requirements.

BLANK PAGE

GROUNDING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Division-26 Basic Materials and Methods sections apply to work specified in this section.

1.2 DESCRIPTION OF WORK:

- A. Provide grounding as specified herein, and as indicated on drawings.
- B. Provide grounding and bonding of all electrical and communication apparatus, machinery, appliances, building components, and items required by the NEC to provide a permanent, continuous, low impedance, grounding system.
- C. Unless otherwise indicated, ground the complete electrical installation including the system neutral, metallic conduits and raceways, boxes, fittings, devices, cabinets, and equipment in accordance with all code requirements.
- D. Ground each separately derived system, as described in NEC Section 250-30, unless otherwise indicated.
- E. Types of grounding in this section include the following:
 - 1. Enclosures
 - 2. Systems
 - 3. Equipment
 - 4. Other items indicated on drawings
- F. Requirements of this section apply to electrical grounding work specified elsewhere in these specifications.

1.3 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to electrical grounding and ground fault protection systems. Comply with applicable ANSI and IEEE requirements. Provide products that have been UL listed and labeled.
- B. Resistance from the service entrance ground bus, through the grounding electrode to earth, shall not exceed 5 ohms.
- **1.4 SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS

2.1 MATERIALS AND COMPONENTS:

- A. GENERAL: Except as otherwise indicated, provide each electrical grounding system as specified herein, and as shown on drawings, including but not necessarily limited to, cables/wires, connectors, terminals (solderless lugs), grounding rods/electrodes and plate electrodes, bonding jumper braid, and other items and accessories needed for complete installation. Where materials or components are not otherwise indicated, comply with NEC, NEMA and established industry standards for applications indicated.
- B. ELECTRICAL GROUNDING CONDUCTORS: Unless otherwise indicated, provide electrical grounding conductors for grounding connections matching power supply wiring

- materials and sized according to NEC. Provide with green insulation.
- C. INSULATED GROUNDING BUSHINGS: Plated malleable iron body with 150 degree Centigrade molded plastic insulating throat, lay-in grounding lug with hardened stainless steel fasteners, OZ-Gedney BLG, or Thomas & Betts #TIGB series.
- D. BONDING JUMPERS: OZ-Gedney Type BJ, or Thomas & Betts #3840 series, or Burndy type GG and type B braid.

PART 3 - EXECUTION

3.1 INSTALLATION OF GROUNDING SYSTEMS:

- A. Install electrical grounding systems in accordance with manufacturer's written instructions and with recognized industry practices to ensure grounding devices comply with requirements.
- B. Install clamp-on connectors only on thoroughly cleaned and metal contact surfaces, to ensure electrical conductivity and circuit integrity.
- C. Provide grounding for the entire raceway, enclosure, equipment and device system in accordance with NEC. All non-metallic raceways shall include copper grounding conductor sized in accordance with NEC. Include copper grounding conductor in all raceway installed in suspended slabs.
- D. Provide service entrance grounding by means of ground rods (quantity of two, driven exterior to building), by means of bonding to water main, and by means of bonding to building structural steel. In addition, provide a grounding electrode for not less than 30 lineal feet in concrete footing or foundation that is in direct contract with earth. Size electrode in accordance with NEC, but in no case, smaller than No. 4 AWG bare copper. Support electrode so as to be below finished grade near the bottom of the trench, and approximately three inches from the bottom or sides of the concrete. Locate a point of connection for inspection.
- E. Provide grounding conductors for dimming systems in accordance with manufacturer's requirement.

3.2 GROUNDING ELECTRODES:

- A. EQUIPMENT BONDING/GROUNDING: Provide a NEC sized conductor, whether indicated or not on the drawings, in raceways as follows:
 - 1. Non-metallic conduits and ducts.
 - Distribution feeders.
 - 3. Device and lighting branch circuits.
 - 4. Provide grounding bushings and bonding jumpers for all conduit terminating in reducing washers, concentric, eccentric or oversized knockouts at panelboards, cabinets and gutters.
- B. Provide bonding jumpers across expansion and deflection couplings in conduit runs, across pipe connections at water meters, and across dielectric couplings in metallic cold water piping system.
- C. Provide bonding wire in all flexible conduit.

3.3 TESTING:

- A. Obtain and record ground resistance measurements both from service entrance ground bus to the ground electrode and from the ground electrode to earth. Install additional bonding and grounding electrodes as required to comply with resistance limits specified under this Section.
- B. Include typewritten records of measured resistance values in the Operation and GROUNDING 26 0526-2

Maintenance Manual.

- C. Use independent testing agency for all testing.
- D. Use test equipment expressly designed for the purpose intended. Submit name of testing agency for review and approval, in writing, to the Engineer prior to the performance of any testing.

BLANK PAGE

SUPPORTING DEVICES

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification section, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is a part of each Division-26 section making reference to supports, anchors, sleeves, and seals, specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of supports, anchors, and sleeves is indicated by drawings and schedules and/or specified in other Division-26 sections. See Section 260532, Raceways, for additional requirements.
- B. Work of this section includes supports, anchors, sleeves and seals required for a complete raceway support system, including but not limited to: clevis hangers, riser clamps, C-clamps, beam clamps, one and two hole conduit straps, offset conduit clamps, expansion anchors, toggle bolts, threaded rods, U-channel strut systems, threaded rods and all associated accessories.

1.3 QUALITY ASSURANCE:

A. Comply with NEC as applicable to construction and installation of electrical supporting devices. Comply with applicable requirements of ANSI/NEMA Std. Pub No. FB 1, "Fittings and Supports for Conduit and Cable Assemblies". Provide electrical components that are UL-listed and labeled.

PART 2 - PRODUCTS

2.1 MANUFACTURED SUPPORTING DEVICES:

A. GENERAL:

1. Provide supporting devices; complying with manufacturer's standard materials, design and construction in accordance with published product information, and as required for a complete installation; and as herein specified. See drawings for additional requirements.

PART 3 - EXECUTION

3.1 INSTALLATION OF SUPPORTING DEVICES:

- A. Install hangers, anchors, sleeves, and seals as required, in accordance with manufacturer's written instructions and with recognized industry practices to ensure supporting devices comply with requirements. Comply with requirements of NECA, NEC and ANSI/NEMA for installation of supporting devices.
- B. Coordinate with other electrical work, including raceway and wiring work, as necessary to interface installation of supporting devices with other work.
- C. Install hangers, supports, clamps and attachments to support piping properly from building structures. Arrange for grouping of parallel runs of horizontal conduits to be supported together on trapeze type hangers where possible. For pre-and post tensioned construction, use pre-set inserts for support of all electrical work. Do not use toggle bolts, moly bolts,

wood plugs or screws in sheetrock or plaster as support for any equipment or raceway.

D. RACEWAYS:

Support raceways that are rigidly attached to structure at intervals not to exceed 8 feet on center, minimum of two straps per 10 foot length of raceway, and within 12" of each junction box, coupling, outlet or fitting. Support raceway at each 90° degree bend. Support raceway (as it is installed) in accordance with the following:

NUMBER OF RUNS	<u>3/4" TO 1-1/4" 0</u>	1-1/2" & LARGER 0		
1	Full straps, clamps or hangers.	Hanger		
2	Full straps, clamps or hangers.	Mounting Channel		
3 or more	Mounting Channel	Mounting Channel		

2. Support suspended raceways on trapeze hanger systems; or individually by means of threaded rod and straps, clamps, or hangers suitable for the application. Do not use independent support wires as a portion of any raceway support system; do not support raceway from ceiling support wires.

E. FLOOR MOUNTED EQUIPMENT:

1. Provide rigid attachment of all floor mounted equipment to the floor slab or structural system. Provide 5/8" bolts or expansion anchors at each 90 degree corner and at intervals not to exceed 48" on center along entire perimeter of the equipment. Provide rigid attachment for all floor mounted switchboards, panelboards, power and control equipment, motor control centers, dimmer cabinets, transformers (provide neoprene vibrations isolators at anchor points), oil switches, battery packs and racks, and similar equipment furnished under Division 26, 27 and 28.

F. WIREWAYS, BUS DUCTS AND CABLE TRAYS:

1. Provide vertical and lateral support systems for all wireways, busway, and cable trays that are supported from overhead structure. See Sections 260536 and 262500 for additional requirements.

CONDUIT RACEWAY

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to electrical raceways and specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of raceways is indicated by drawings and schedules.
- B. Types of raceways in this section include the following:
 - 1. Electrical Metallic Tubing
 - 2. Flexible Metal Conduit
 - Intermediate Metal Conduit
 - 4. Liquid-tight Flexible Metal Conduit
 - 5. Rigid Metal Conduit
 - 6. Rigid Non-metallic Conduit

1.3 QUALITY ASSURANCE:

- A. MANUFACTURERS: Firms regularly engaged in manufacture of raceway systems of types and sizes required, whose products have been in satisfactory use in similar service for not less than three (3) years.
- B. STANDARDS: Comply with applicable portions of NEMA standards pertaining to raceways. Comply with applicable portions of UL safety standards pertaining to electrical raceway systems; and provide products and components that have been UL-listed and labeled. Comply with NEC requirements as applicable to construction and installation of raceway systems.
- C. SUBMITTALS: Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS

2.1 METAL CONDUIT AND TUBING:

- A. GENERAL:
 - 1. Provide metal conduit, tubing and fittings of types, grades, sizes and weights (wall thicknesses) as indicated; with minimum trade size of 3/4".
- B. RIGID METAL CONDUIT (RMC): FS WW-C-0581 and ANSI C80.1.
- C. INTERMEDIATE STEEL CONDUIT (IMC): FS WW-C-581.
- D. ALUMINUM CONDUIT: Not acceptable.
- E. MC CABLE: Not acceptable.
- F. RIGID AND INTERMEDIATE STEEL CONDUIT FITTINGS:
 - 1. Provide fully threaded malleable steel couplings; raintight and concrete tight where required by application. Provide double locknuts and metal bushings at all conduit terminations. Install OZ Type B bushings on conduits 1-1/4" and larger.

- G. ELECTRICAL METALLIC TUBING (EMT): FS WW-C-563 and ANSI C80.3.
- H. EMT FITTINGS:
 - 1. Provide insulated throat nylon bushings with non-indenter type malleable steel fittings at all conduit terminations. Install OZ Type B bushings on conduits 1" larger. Cast or indenter type fittings are not acceptable.
- I. FLEXIBLE METAL CONDUIT: FS WW-C-566, of the following type;
 - Zinc-coated steel.
- J. FLEXIBLE METAL CONDUIT FITTINGS: FS W-F-406, Type 1, Class 1, and Style A.
- K. EXPANSION FITTINGS: OZ Type AX, or equivalent to suit application.

2.2 NON-METALLIC CONDUIT AND DUCTS:

A. GENERAL: Not acceptable.

2.3 CONDUIT; TUBING; AND DUCT ACCESSORIES:

A. Provide conduit, tubing and duct accessories of types and sizes, and materials, complying with manufacturer's published product information, that mate and match conduit and tubing. Provide manufactured spacers in all duct bank runs.

2.4 SEALING BUSHINGS:

A. Provide OZ Type FSK, WSK, or CSMI as required by application. Provide OZ type CSB internal sealing bushings.

2.5 CABLE SUPPORTS:

A. Provide OZ cable supports for vertical risers, type as required by application.

PART 3 - EXECUTION

3.1 INSTALLATION OF ELECTRICAL RACEWAYS:

- A. Install electrical raceways where indicated; in accordance with manufacturer's written instructions, applicable requirements of NEC and NECA "Standard of Installation", and in accordance with the following:
 - 1. SERVICE ENTRANCE CONDUCTORS, AND CONDUCTORS OVER 600 VOLTS:
 - a. Install in rigid metal conduit (RMC), or intermediate metal conduit (IMC); except where buried below grade, install in non-metallic conduit or duct, individually encased in concrete. See duct banks.

2. FEEDERS UNDER 600 VOLTS:

- a. Install feeders to panels and motor control centers and individual equipment feeders rated 100 amps and greater, in rigid metal conduit (RMC), or intermediate metal conduit (IMC), or Electrical Metallic Tubing (EMT); except where buried below grade, install in non-metallic conduit or duct. Encase feeders 1-1/4" and larger, individually in concrete where installed below grade. See duct banks.
- 3. BRANCH CIRCUITS, SIGNAL AND CONTROL CIRCUITS, AND INDIVIDUAL EQUIPMENT CIRCUITS RATED LESS THAN 100 AMPS:
 - a. Install in electric metallic tubing (EMT).
- B. Coordinate with other work including metal and concrete deck work, as necessary to interface installation of electrical raceways and components.

CONDUIT RACEWAY 26 0532-2

© BNA Consulting

- C. Install raceway in accordance with the following:
 - 1. Provide a minimum of 12" clearance measured from outside of insulation from flues, steam and hot water piping, etc. Avoid installing raceways in immediate vicinity of boilers and similar heat emitting equipment. Conceal raceways in finished walls, ceilings and floor (other than slab-on-grade), except in mechanical, electrical and/or communication rooms, conceal all conduit and connections to motors, equipment, and surface mounted cabinets unless exposed work is indicated on the drawings. Run concealed conduits in as direct a line as possible with gradual bends. Where conduit is exposed in mechanical spaces, etc., install parallel with or at right angles to building or room structural lines. Do not install lighting raceway until piping and duct work locations have been determined in order to avoid fixtures being obstructed by overhead equipment.
 - 2. Where cutting raceway is necessary, remove all inside and outside burrs; make cuts smooth and square with raceway. Paint all field threads (or portions of raceway where corrosion protection has been damaged) with primer and enamel finish coat to match adjacent raceway surface.
 - 3. Provide a minimum of 1 ½" from nearest surface of the roof decking to raceway.
 - 4. Provide a maximum of three phase conductors in any one conduit or as approved by electrical engineer. Where phase conductors share a common neutral they must have a means to simultaneously disconnect all ungrounded conductors at the point where the branch circuits originate. The ungrounded and neutral conductors of a multi-wire branch circuit must be grouped together by wire ties at the point of origination. Provide one size larger neutral conductor than the branch circuit conductor for all multi-wire branch circuits.
 - 5. Provide neutral and ground wire as specified elsewhere in documents.
 - 6. Provide separate neutral conductor for all single phase branch circuits installed. No shared neutrals are allowed. Neutral conductor shall be the same size as the phase conductor.
- D. Comply with NEC for requirements for installation of pull boxes in long runs.
- E. Cap open ends of conduits and protect other raceways as required against accumulation of dirt and debris. Pull a mandrel and swab through all conduit before installing conductors. Install a 200 lb. nylon pull cord in each empty conduit run.
- F. Replace all crushed, wrinkled or deformed raceway before installing conductors.
- G. Provide rigid metal conduit (RMC) for all bends greater than 22 degrees in buried conduit. Provide protective coating for RMC bend as specified herein.
- H. Where raceways penetrate building, area ways, manholes or vault walls and floors below grade, install rigid metal conduit (RMC) for a minimum distance of 10 feet on the exterior side of the floor or wall measured from interior face. Provide OZ, Type FSK, WSK or CSMI sealing bushings (with external membrane clamps as applicable) for all conduit penetrations entering walls or slabs below grade. Provide segmented type CSB internal sealing bushings in all raceways penetrating building walls and slabs below grade, and in all above grade raceway penetrations susceptible to moisture migration into building through raceway.
- I. Install liquid-tight flexible conduit for connection of motors, transformers, and other electrical equipment where subject to movement and vibration.
- J. Install spare 3/4" conduits (capped) from each branch panelboard into the ceiling and floor space. Run five into the ceiling space and five into the floor space. Where the floor is not accessible run six conduits into the ceiling space. Run conduits the required distance necessary to reach accessible ceiling space.
- K. Provide OZ expansion fittings on all conduits crossing building expansion joints, both in slab and suspended.

CONDUIT RACEWAY 26 0532-3

© BNA Consulting

- L. Provide OZ cable supports in all vertical risers in accordance with NEC 300-19; type as required by application.
- M. Complete installation of electrical raceways before starting installation of cables/conductors within raceways.
- N. Raceway installation below grade:
 - 1. Apply protective coating to metallic raceways in direct contact with earth or fill of any type; consisting of spirally wrapped PVC tape (1/2" minimum overlap of scotch wrap tape or equal); or factory applied vinyl cladding (minimum thickness .020 inches). Completely wrap and tape all field joints.
 - 2. Burial depths must comply with NEC Section 300-5 but in no case be less than 24", unless noted otherwise on drawings.

O. DUCTBANKS:

- 1. Provide ductbank construction as indicated using 3000 psi at 28 day strength concrete. Use Type II low alkali per ASTM C150. Use ASTM C-33 aggregate gradation with maximum size of 3/4". Use W/C ratio of 0.50. Install #4 reinforcing bar per ASTM 615 grade 50 in each corner of ductbank. Provide minimum 4" concrete cover on all sides of exterior conduits. Provide polypropylene pull rope in all spare duct.
- P. Electrical Identification: Refer to Section 260553 for requirements.
- Q. SPARE PARTS: Refer to Section 26 0502 for requirements.

ELECTRICAL BOXES AND FITTINGS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specifications sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is a part of each Division-26, 27 and 28 section making reference to electrical wiring boxes and fittings specified herein. See Section 260532, Raceways, for additional requirements.

1.2 DESCRIPTION OF WORK:

- A. The extent of electrical box and electrical fitting work is indicated by drawings and schedules.
- B. Types of electrical boxes and fittings in this section include the following:
 - 1. Outlet Boxes
 - Junction Boxes
 - 3. Pull Boxes
 - 4. Floor Boxes
 - Conduit Bodies
 - Bushings
 - 7. Locknuts
 - 8. Knockout Closures
 - 9. Miscellaneous Boxes and Fittings

1.3 QUALITY ASSURANCE:

- A. Comply with NEC as applicable to construction and installation of electrical boxes and fittings. Comply with ANSI C 134,1 (NEMA Standards Pub No. OS 1) as applicable to sheet-steel outlet boxes, device boxes, covers and box supports. Provide electrical boxes and fittings that have been UL-listed and labeled.
- **1.4 SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS

2.1 FABRICATED MATERIALS:

A. INTERIOR OUTLET BOXES:

- 1. Provide one piece, galvanized flat rolled sheet steel interior outlet wiring boxes with accessory rings, of types, shapes and sizes, including box depths, to suit each respective location and installation, construct with stamped knockouts in back and sides, and with threaded screw holes with corrosion-resistant screws for securing box and covers and wiring devices; minimum size 4"x4"x2-1/8".
- 2. Provide an 'FS' box, with no knockouts when surface mounted in a finished, nonutility space. Surface mounting is only acceptable when approved by the Architect.
- B. INTERIOR OUTLET BOX ACCESSORIES:

1. Provide outlet box accessories as required for each installation, including mounting brackets, hangers, extension rings, fixture studs, cable clamps and metal straps for supporting outlet boxes, that are compatible with outlet boxes being used and fulfilling requirements of individual wiring applications.

C. JUNCTION AND PULL BOXES:

1. Provide code-gage sheet steel junction and pull boxes, with screw-on covers; of types, shapes and sizes to suit each respective location and installation; with welded seams and equipped with stainless steel nuts, bolts, screws and washers.

D. CONDUIT BODIES:

1. Provide galvanized cast-metal conduit bodies, of types, shapes and sizes to suit respective locations and installation, construct with threaded-conduit-entrance ends, removable covers, and corrosion-resistant screws.

E. BUSHINGS, KNOCKOUT CLOSURES AND LOCKNUTS:

1. Provide corrosion-resistant punched-steel box knockout closures, conduit locknuts and malleable steel conduit bushings and offset connectors, of types and sizes to suit respective uses and installation.

PART 3 - EXECUTION

3.1 INSTALLATION OF ELECTRICAL BOXES AND FITTINGS:

A. GENERAL:

- 1. Install electrical boxes and fittings where indicated, complying with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.
- 2. Coordinate installation of electrical boxes and fittings with wire/cable and raceway installation work.
- 3. Provide coverplates for all boxes. See Section 262726, Wiring Devices.
- 4. Provide weatherproof outlets for interior and exterior locations exposed to weather or moisture.
- 5. Provide knockout closures to cap unused knockout holes where blanks have been removed.
- 6. Install boxes and conduit bodies to ensure ready accessibility of electrical wiring. Do not install boxes above ducts or behind equipment. Install recessed boxes with face of box or ring flush with adjacent surface. Seal between switch, receptacle and other outlet box openings and adjacent surfaces with plaster, grout, or similar suitable material.
- 7. Fasten boxes rigidly to substrates or structural surfaces, or solidly embed electrical boxes in concrete or masonry. Use bar hangers for stud construction. Use of nails for securing boxes is prohibited. Set boxes on opposite sides of common wall with minimum 10" of conduit between them. Set boxes on opposite sides of fire resistant walls with minimum of 24" separation.
- 8. Provide a minimum of 1 ½" from the nearest surface of the roof decking to the installed boxes.
- 9. Provide electrical connections for installed boxes.

ELECTRICAL SEISMIC CONTROL

PART 1 - GENERAL

1.1 WORK INCLUDED:

- A. Anchorage and seismic restraint systems for all Division 26 isolated and non-isolated equipment, cable tray, and conduit systems.
- B. Anchorage and seismic restrain systems for electrical components shall include but not be limited to the following:
 - 1. Pad Mounted Equipment
 - 2. Conduit

1.2 RELATED WORK:

- A. Requirements: Provide Electrical Seismic Control in accordance with the Contract Documents.
- B. Section 260500 Electrical General Provisions

1.3 REFERENCES:

- A. International Building Code, Current Edition in use by Jurisdictional Authority.
- B. NFPA Bulletin 90A, Current Edition.
- C. UL Standard 181.
- D. ASCE 7-10

1.4 SYSTEM DESCRIPTION

- A. The Division 26 Contractor shall be responsible for supplying and installing equipment, vibration isolators, flexible connections, rigid steel frames, anchors, inserts, hangers and attachments, supports, seismic snubbers and bracing to comply with the following:
 - 1. Short period design spectral response acceleration coefficient SDS=0.70.
 - 2. One second period design spectral response acceleration coefficient SD1=0.28.
 - 3. Site Class B.
 - 4. Seismic Design Category D.
 - 5. Importance Factor (Ip) = 1.0
- B. Seismic Restraint Exceptions
 - 1. The following components are exempt from the requirements of this section

1.5 QUALITY ASSURANCE:

- A. All supports, hangers, bases, anchorage and bracing for all isolated equipment and non-isolated equipment shall be designed by a professional engineer licensed in the state where the project is located, employed by the restraint manufacturer, qualified with seismic experience in bracing for electrical equipment. Shop drawings submitted for earthquake bracing and anchors shall bear the Engineer's signed professional seal. All calculations/design work required for the seismic anchorage and restraint of all Division 26 equipment and systems shall be provided by a single firm.
- B. The above qualified seismic engineer shall determine specific requirements for equipment anchorage and restraints, locations and sizes based on shop drawings for the electrical equipment that have been submitted, reviewed and accepted by the

Architect/Engineer for this project.

- C. Seismic Engineer or the Engineer's Representative shall field inspect final installation and certify that bracing and anchorage are in conformance with the Seismic Engineer's design. A certificate of compliance bearing the Seismic Engineer's signed Professional Engineer's seal shall be submitted and shall be included in each copy of the Operation and Maintenance Manuals.
- D. The Division 26 Contractor shall require all equipment suppliers furnish equipment that meets the seismic code, with bases/skids/curb designed to receive seismic bracing and/or anchorage. All isolated and non-isolated electrical equipment bracing to be used in the project shall be designed from the Equipment Shop Drawings and certified correct by the equipment manufacturer for seismic description listed in Paragraph 1.4 above, with direct anchorage capability.
- **1.6 SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS:

2.1 RESTRAINT EQUIPMENT AND SYSTEMS:

- A. Acceptable Manufacturers and Suppliers for Non-Isolated Systems:
 - 1. Mason Industries, Inc.
 - 2. Korfund
 - 3. Amber/Booth Company
 - 4. Vibration Mountings and Control Company
 - 5. Kinetics
 - 6. International Seismic Application Technology
 - 7. Tolco
- B. Manufacture and design of restraints and anchors for isolated equipment shall be by the manufacturer of the vibration isolators furnished for the equipment.

2.2 SNUBBERS:

- A. Snubbers shall be all-directional and consist of interlocking steel members restrained by replaceable shock absorbent elastomeric materials a minimum of 3/4 inch thick.
- B. Snubbers shall be manufactured with an air gap between hard and resilient material of not less than 1/8 inch or more than 1/4 inch.
- C. Snubbers shall be Mason Industries Z -1011 or accepted equivalent.

PART 3 - EXECUTION

3.1 DESIGN AND INSTALLATION:

A. General:

- 1. All electrical components shall be braced, anchored, snubbed or supported to withstand seismic disturbances in accordance with the criteria of this specification. Provide all engineering, labor, materials, and equipment for protection against seismic disturbances as specified herein. The following electrical components are exempt from seismic restraint requirements.
 - a. Electrical components in Seismic Design Category A or B (see section 1.4)
 - b. Electrical components in Seismic Design Category C provided that the component importance factor, I_p , is equal to 1.0 (see section 1.4).

- c. Electrical components in Seismic Design Categories D, E, or F where all of the following apply:
 - i. The component importance factor, I_p , is equal to 1.0;
 - ii. The component is positively attached to the structure;
 - iii. Flexible connections are provided between the component and associated ductwork, piping, and conduit; and either
 - The component weighs 400 lb (1,780 N) or less and has a center of mass located 4 ft (1.22 m) or less above the adjacent floor level; or
 - 2. The component weighs 20 lb (89 N) or less or, in the case of a distributed system, 5 lb/ft (73 N/m) or less.
- 2. Powder-actuated fasteners (shot pins) shall not be used for component anchorage in tension applications in Seismic Design Category D, E, or F.
- 3. Attachments and supports for electrical equipment shall meet the following provisions:
 - a. Attachments and supports transferring seismic loads shall be constructed of materials suitable for the application and designed and constructed in accordance with a nationally recognized structural code such as, when constructed of steel, AISC, Manual of Steel Construction (Ref. 9.8-1 or 9.8-2).
 - b. Friction clips shall not be used for anchorage attachment.
 - c. Expansion anchors shall not be used for electrical equipment rated over 10 hp (7.45 kW). Exception: Undercut expansion anchors.
 - d. Drilled and grouted-in-place anchors for tensile load applications shall use either expansive cement or expansive epoxy grout.
 - e. Supports shall be specifically evaluated if weak-axis bending of light-gauge support steel is relied on for the seismic load path.
 - f. Components mounted on vibration isolation systems shall have a bumper restraint or snubber in each horizontal direction. The design force shall be taken as 2Fp. The intent is to prevent excessive movement and to avoid fracture of support springs and any non- ductile components of the isolators.
 - g. Seismic supports shall be constructed so that support engagement is maintained.

B. Pad Mounted Equipment

- 1. Spring Isolated Equipment:
 - a. All vibration isolated equipment shall be mounted on rigid steel frames or concrete bases as described in the vibration control specifications unless the equipment manufacturer certified direct attachment capability. Each spring mounted base shall have a minimum of four all-directional seismic snubbers that are double acting and located as close to the vibration isolators as possible to facilitate attachment both to the base and the structure. Snubbers shall be installed with factory set clearances.

2. Non-Isolated Equipment:

a. The section 260548 (Electrical Seismic Control) Contractor shall be responsible for thoroughly reviewing all drawings and specifications to determine all equipment i.e. switchboards, transformers, generators, etc. to be restrained. This Contractor shall be responsible for certifying that this equipment is mounted and braced such that it adheres to the system description criteria in part 1.4 of this specification section.

C. Conduit, Conduit Racks/Trapeze Assemblies, Cable Tray and Bus Duct:

- 1. Seismic braces for be omitted when the distance from the supporting structure to the raceway support point is 12" or less. Where rod hangers are used, they shall be equipped with swivels to prevent inelastic bending in the rod.
- 2. Seismic braces may be omitted where the total weight of the assembly is less than 10 lb/ft.
- 3. Seismic braces for individual conduit may be omitted for conduit less than 2.5 inch trade size.
- 4. A rigid conduit system shall not be braced to dissimilar parts of a building or two dissimilar building systems that may respond in a different mode during an earthquake. Examples: Wall and a roof; solid concrete wall and a metal deck with lightweight concrete fill.
- 5. Unbraced conduit attached to in-line equipment shall be provided with adequate flexibility to accommodate differential displacements.
- 6. At the interface of adjacent structures or portions of the same structure that may move independently, utility lines shall be provided with adequate flexibility to accommodate the anticipated differential movement between the ground and the structure.
- 7. Provide large enough pipe sleeves through wall or floors to allow for anticipated differential movements.
- 8. For spaces, where the Importance Factor (Ip) is equal to 1.5, all electrical components that are attached to structures that could displace relative to one another and for isolated structures where components cross the isolation interface, the components shall be designed to accommodate the eismic relative dispalcements.

ELECTRICAL IDENTIFICATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Requirements of the following Division 26 Sections apply to this section:
 - 1. "Basic Electrical Requirements".
 - 2. "Basic Electrical Materials and Methods".

1.2 SUMMARY

- A. This section includes identification of electrical materials, equipment and installations. It includes requirements for electrical identification components including but not limited to the following:
 - 1. Identification labels for raceways, cables and conductors.
 - 2. Operational instruction signs.
 - 3. Warning and caution signs.
 - 4. Equipment labels and signs.
- B. Related Sections: The following sections contain requirements that relate to this section:
- C. Division 9 Section "Painting" for related identification requirements.
- D. Refer to other Division 26 sections for additional specific electrical identification associated with specific items.

1.3 QUALITY ASSURANCE

- A. Electrical Component Standard: Components and installation shall comply with NFPA 70 "National Electrical Code"
- **1.4 SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - 1. American Labelmark Co.
 - 2. Calpico, Inc.
 - Cole-Flex Corp.
 - 4. Emed Co., Inc.
 - 5. George-Ingraham Corp.
 - 6. Ideal Industries, Inc.
 - 7. Kraftbilt
 - 8. LEM Products, Inc.
 - 9. Markal Corp
 - 10. National Band and Tag Co.

- 11. Panduit Corp.
- 12. Radar Engineers Div., EPIC Corp.
- 13. Seton Name Plate Co.
- 14. Standard Signs, Inc.
- 15. W.H Brady, Co.

2.2 ELECTRICAL IDENTIFICATION PRODUCTS

- A. Colored Conduit Systems for raceway identification:
 - 1. Factory-painted conduit and/or factory-painted couplings and fittings
- B. Colored paint for raceway identification:
 - 1. Use <u>Kwal Paint</u> colors as specified in Part 3 Execution.
- C. Color Adhesive Marking Tape for Raceways, Wires and Cables:
 - 1. Self-adhesive vinyl tape not less than 3 mills thick by 1" to 2" in width.
- D. Wire/Cable Designation Tape Markers:
 - Vinyl or vinyl-cloth, self-adhesive, wraparound, cable/conductor markers with preprinted numbers and letters.
- E. Brass or Aluminum Tags:
 - 1. Metal tags with stamped legend, punched for fastener.
 - 2. Dimensions: 2" X 2" 19 gage.
- F. Engraved, Plastic Laminated Labels, Signs and Instruction Plates:
 - 1. Engraving stock plastic laminate, 1/16" minimum thickness for signs up to 20 sq. in. or 8" in length; 1/8 " thick for larger sizes. Engraved legend in 1/4" high white letters on black face and punched for mechanical fasteners.
- G. Equipment Labels:
 - Adhesive backed polyester with self-laminating flap. Chemical, abrasion and heat resistant.
 - 2. Dimensions: minimum 5" x 2"
 - 3. Conductor-Identification-Means Labels:
 - a. Information contained: the method utilized for identifying ungrounded conductors within switchboards, distribution panels and branch circuit panels.
 - 4. Available-Fault-Current Labels:
 - a. Information contained: maximum available fault current at the respective piece of equipment, and date of calculation of fault current.
 - 5. Source-of-Supply Labels:
 - a. Information contained: indicate the device or equipment where the power supply originates.
- H. Baked Enamel Warning and Caution Signs for Interior Use:
 - 1. Preprinted aluminum signs, punched for fasteners, with colors legend and size appropriate to location.
- I. Fasteners for Plastic-Laminated and Metal Signs:
 - Self-tapping stainless steel screws or # 10/32 stainless steel machine screws with nuts, flat and lock washers.
- J. Cable Ties:

1. Fungus-inert, self-extinguishing, one-piece, self-locking nylon cable ties, 0.18" minimum width, 50-lb. Minimum tensile strength, and suitable for a temperature range from minus 40° F. to 185° F. Provide ties for specified colors when used for color coding.

PART 3 – EXECUTION

3.1 INSTALLATION

- A. Lettering and Graphics:
 - Coordinate names, abbreviations, colors and other designations used in electrical identification work with corresponding designations specified or indicated. Install numbers, lettering and colors as approved in submittals and as required by code.
- B. Install identification devices in accordance with manufacturer's written instructions and requirements of NEC.
- C. Sequence of Work:
 - 1. Where identification is to be applied to surfaces that require a finish, install identification after completion of finish work.
 - 2. Identify Junction, Pull and Connection Boxes.
 - a. Code-required caution sign for boxes shall be pressured-sensitive, self-adhesive label indication system voltage in black, preprinted on orange background. Install on outside of box cover. Also label box covers on outside of cover with identity of contained circuits. Use pressure-sensitive plastic labels at exposed locations and similar labels or plasticized card stock tags at concealed boxes.
- D. Conductor Color Coding.
 - 1. Provide color coding for secondary service, feeder and branch circuit conductors throughout the project secondary electrical system as follows:

CONDUCTOR	208Y / 120V System	480Y / 277V System
Phase A	Black	Brown
Phase B	Red	Orange
Phase C	Blue	Yellow
Shared/Single Neutral	White	Gray
Neutral A (dedicated)	White w/Black Stripe	Gray w/Black Stripe
Neutral B (dedicated)	White w/Red Stripe	Gray w/Orange Stipe
Neutral C (dedicated)	White w/Blue Stripe	Gray w/Yellow Stipe
Equipment Ground	Green	Green
Isolated Ground	Green w/Yellow Strip	Green w/Yellow Stripe

- 2. Switch legs, travelers and other wiring for branch circuits shall be of colors other than those listed above.
- 3. Use conductors with color factory applied the entire length of the conductors except as follows:
 - a. The following field-applied color-coding methods may be used in lieu of factory-coded wire for sizes larger than No. 10 AWG.

- b. Apply colored, pressure-sensitive plastic tape in half-lapped turns for a distance of 6 inches from terminal points and in boxes where splices or taps are made. Apply the last two laps of tape with no tension to prevent possible unwinding. Use 1-inch-wide tape in colors as specified. Do not obliterate cable identification markings by taping. Tape locations may be adjusted slightly to prevent such obliteration.
- c. In lieu of pressure-sensitive tape, colored cable ties may be used for color identification. Apply three ties of specified color to each wire at each terminal or splice point starting 3 inches from the terminal and spaced 3 inches apart. Apply with a special tool or pliers, tighten for snug fit, and cut off excess length.

E. Power Circuit Identification.

- Securely fasten identifying metal tags or aluminum wraparound marker bands to cables, feeders, and power circuits in vaults, pull boxes, junction boxes, manholes, and switchboard rooms with 1/4-inch steel letter and number stamps with legend to correspond with designations on Drawings. If metal tags are provided, attach them with approximately 55-lb monofilament line or one-piece self-locking nylon cable ties.
- 2. Tag or label conductors as follows:
 - a. Future Connections: Conductors indicated to be for future connection or connection under another contract with identification indicting source and circuit numbers.
 - b. Multiple Circuits: Where multiple branch circuits or control wiring or communications/ signal conductors are present in the same box or enclosure (except for three-circuit, four-wire home runs), label each conductor or cable. Provide legend indicating source, voltage, circuit number, and phase for branch circuit wiring. Phase and voltage of branch circuit wiring may be indicated by mean of coded color of conductor insulation. For control and communications/signal wiring, use color coding or wire/cable marking tape at terminations and at intermediate locations where conductors appear in wiring boxes, troughs, and control cabinets. Use consistent letter/number conductor designations throughout on wire/cable marking tapes.
- 3. Match identification markings with designations used in panelboards shop drawings, Contract Documents, and similar previously established identification schemes for the facility's electrical installations.
- F. Apply warning, caution and instruction signs and stencils as follows:
 - 1. Install warning, caution, or instruction signs where required by NEC, where indicated, or where reasonably required to assure safe operation and maintenance of electrical systems and of the items they connect. Install engraved plastic-laminated instruction signs with approved legend where instructions or explanations are needed for system or equipment operation. Install butyrate signs with metal backing for outdoor items. Warning and caution signs shall be furnished and installed on, but not be limited to the following equipment and locations:
 - a. Entrances to rooms and other guarded locations that contain exposed live parts 600 volts or less; signs shall forbid unqualified personnel to enter.
 - b. Switch and Overcurrent device enclosures with splices, taps and feed-through conductors. Provide warning label on the enclosures that identifies the nearest disconnecting means for any feed-through conductors.
 - c. Entrances to buildings, vaults, rooms or enclosures containing exposed live parts or exposed conductors operating at over 600 volts: DANGER-HIGH VOLTAGE-KEEP OUT.

- d. Metal-enclosed switchgear, unit substations, transformers, enclosures, pull boxes, connection boxes and similar equipment operating at over 600 volts shall have appropriate caution signs and warning labels.
- e. Indoor and Outdoor substations operating over 600 volts. Provide warning signs, instructional signs and single-line diagrams in accordance with NEC 225.70.
- G. Install equipment/system circuit/device identification as follows:
 - 1. Apply equipment identification labels of engraved plastic-laminate on each major unit of electrical equipment in building, including central or master unit of each electrical system. This includes communication/signal/alarm systems, unless unit is specified with its own self-explanatory identification. Except as otherwise indicated, provide single line of text, with 1/4"-high lettering on 1-inch-high label (1 1/2-inch-high where two lines are required) white lettering in black field. White lettering in red field for Emergency Power Systems. Text shall match terminology and numbering of the Contract Documents and shop drawings. Apply labels for each unit of the following categories of electrical equipment.
 - a. Lighting Control Equipment.
- H. The label shall identify the device or equipment where the power supply originates, and the system voltage and phase. For example: Feeder Power Supply for Panel "XX" Originates at Panel "XX" (or Switchboard "XX", Transformer "XX", Switch "XX", etc.); 120/208 volts, 3-phase (or 120/240, 277/480, etc.).
- I. Apply circuit/control/item designation labels of engraved plastic laminate for disconnect switches, breakers, pushbuttons, pilot lights, motor control centers, and similar items for power distribution and control components above, except panelboards and alarm/signal components, where labeling is specified elsewhere.
- J. Install labels at locations indicated and at locations for best convenience of viewing without interference with operation and maintenance of equipment.
- K. Mark each device box (for each type of wiring device) with a permanent ink felt tip marker, indicating the circuit that the device is connected to: Example; "CKT A-1"

BLANK PAGE

WIRING DEVICES

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to wiring devices specified herein.

1.2 DESCRIPTION OF WORK:

- A. The extent of wiring device work is indicated by drawings and schedules. Wiring devices are defined as single discrete units of electrical distribution systems that are intended to carry but not utilize electric energy.
- B. Types of electrical wiring devices in this section include the following:
 - 1. Cord caps
 - 2. Cord connectors
 - Wall plates

1.3 QUALITY ASSURANCE:

- A. Comply with NEC and NEMA standards as applicable to construction and installation of electrical wiring devices. Provide electrical wiring devices that have been UL listed and labeled.
- **1.4 SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 - PRODUCTS

2.1 FABRICATED WIRING DEVICES:

A. GENERAL:

1. Provide factory-fabricated wiring devices, in types, and electrical ratings for applications indicated and complying with NEMA Stds. Pub No. WD 1.

B. CORD CAPS AND CONNECTORS:

- 1. Provide 3, 4 and 5-wire grounding, cap plugs, and connectors of ampere and voltage rating required, for final equipment, and as indicated otherwise on drawings.
- 2. Provide products of one of the following:
 - a. Cooper
 - b. General Electric
 - c. Hubbell
 - d. Leviton
 - e. P&S

2.2 WIRING DEVICE ACCESSORIES:

A. WALL PLATES:

 Provide coverplates for wiring devices; plate color to match attached wiring devices. Provide Lexan (stainless steel) coverplates in all finished areas. Provide galvanized steel plates in unfinished areas. Provide blank coverplates for all empty outlet boxes.

PART 3 – EXECUTION

3.1 GENERAL

- A. Install wiring devices as indicated, in compliance with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation" and in accordance with recognized industry practices to fulfill project requirements.
- B. Coordinate with other work, including painting, electrical box and wiring work, as necessary to interface installation of wiring devices with other work. Install devices in boxes such that front of device is flush and square with coverplate.
- C. Install wiring devices only in electrical boxes that are clean; free from excess building materials, dirt, and debris.
- D. Install blank plates on all boxes without devices.
- E. Delay installation of wiring devices until wiring work and painting is completed. Provide separate neutral conductor from panel to each GFI receptacle.
- F. Install GFI receptacles for all receptacles installed in the following locations:
 - 1. Restrooms, locker rooms, kitchens, within 6 feet of any sink, or when serving vending machines and electric drinking fountains.
 - 2. Indoor wet locations, non-dwelling garages, elevator rooms and pits.
 - 3. Outdoors, and on rooftops.
 - 4. Dwelling unit garages, crawlspaces and unfinished basements, accessory buildings, boathouses, and receptacles for boat hoists.
- G. Where light switches or wall box dimmers are specified, provide a separate neutral for each phase of the branch circuits that switches or dimmers are connected.
- H. Electrical Identification: Refer to Section 260553 for requirements.

3.2 PROTECTION OF WALL PLATES AND RECEPTACLES:

A. At time of substantial completion, replace those items, that have been damaged, including those stained, burned and scored.

3.3 GROUNDING:

A. Provide electrically continuous, tight grounding connections for wiring devices, unless otherwise indicated.

3.4 TESTING:

A. Prior to energizing circuitry, test wiring devices for electrical continuity and proper polarity connections. After energizing circuitry, test wiring devices to demonstrate compliance with requirements.

OVERCURRENT PROTECTIVE DEVICES

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to overcurrent protective devices specified herein.

1.2 DESCRIPTION OF WORK:

- A. Extent of overcurrent protective device work is indicated by drawings and schedules and specified herein. Overcurrent protective devices specified herein are for installation as individual components in separate enclosures; and for installation as integral components of switchboard and panelboards. See Section 262413, Switchgear and Switchboards, and Section 262416, Panelboards.
- B. Types of overcurrent protective devices in this section include the following for operation at 600 Volts and below:
 - Insulated case circuit breakers
- C. Refer to other Division-26 sections for cable/wire and connector work required in conjunction with overcurrent protective devices.

1.3 QUALITY ASSURANCE

- A. Comply with NEC requirements and NEMA and ANSI standards as applicable to construction and installation of overcurrent devices.
- **1.4 SUBMITTALS:** Refer to Section 26 0502 for requirements.

PART 2 – PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

- A. Subject to compliance with requirements, provide products of one of the following (main and branch device manufacturer must be same as panelboard and/or switchboard manufacturer):
- B. CIRCUIT BREAKERS:
 - 1. Cutler Hammer Products, Eaton Corp.
 - GE/ABB
 - Square D Co.
 - 4. Siemens Energy and Automation

C. INSULATED CASE CIRCUIT BREAKERS

- Provide factory-assembled, motorized, insulated case circuit breakers for power distribution switchgear and switchboards. Provide breakers of amperage, voltage and RMS interrupting rating shown, with solid-state trip mechanisms and with motorized circuit breaker charging mechanism. Breakers shall be UL listed for application at 100% of their continuous ampere rating.
- 2. Circuit breakers 1200 amps and larger shall be insulated case circuit breakers.

- 3. Solid-state trip mechanisms shall have the following functions: Adjustable long time ampere rating; adjustable long time delay; adjustable short time pick up; adjustable short time delay and adjustable instantaneous pick up.
- 4. Provide protective relaying to allow for long time, short time, instantaneous settings with over/under voltage and current imbalance trip. Include phase failure protection relay protection.
- 5. Provide an energy-reducing maintenance switch with local, lit status indicator to allow for a reduction of the instantaneous pickup and instantaneous delay settings for use during maintenance. Device shall mount in face of dead-front. The switch shall be provided by the same manufacturer as the circuit breaker.

PART 3 - EXECUTION

3.1 INSTALLATION OF OVERCURRENT PROTECTIVE DEVICES:

- A. Install overcurrent protective devices as indicated, in accordance with the manufacturer's written instructions and with recognized industry practices to ensure that protective devices comply with requirements. Comply with NEC and NEMA standards for installation of overcurrent protective devices.
- B. Coordinate with work as necessary to interface installations of overcurrent protective devices with other work.
- C. Install fuses in overcurrent protective devices. For motor circuits, fuse sizes shown on drawings are for general guidance only. Size fuses in accordance with fuse manufacturer's recommendation for given motor nameplate ampere rating. Test operation. If nuisance tripping occurs, increase fuse size and disconnect device (if necessary) as required to provide nuisance free tripping. Adjust fuse size properly for ambient temperature, frequent starting and stopping of motor loads, and for loads with long start times. Include all costs in bid.
- D. After the switchgear is energized and just prior to Substantial Completion, the contractor shall ensure that the field-adjustable circuit breakers and solid-state circuit breakers and associated trip mechanisms have been set to the appropriate settings as recommended by the equipment. Time-current trip curves and trip setting information as was required in the Submittal portion of this specification shall be made available by the contractor at this time.
- E. Field test all protective relay devices for proper operation; test to be performed by representative of the manufacturer. Include verification of complete time current trip characteristics.
- F. Electrical Identification: Refer to Section 260553 for requirements.

3.2 FIELD QUALITY CONTROL

A. Prior to energization of overcurrent protective devices, test devices for continuity of circuitry and for short-circuits. Correct malfunctioning units, and then demonstrate compliance with requirements.

DEMOLITION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Special Provisions, Division 1 and Division-2 Specification sections, apply to work of this section.
- B. This section is a Division-26 Basic Materials and Methods section, and is part of each Division-26 section making reference to demolition.

1.2 DESCRIPTION OF WORK:

- A. Extent of major items of demolition work is indicated by drawings. Other demolition work shall be performed as required to maintain system operation.
- B. The intent of the drawings is to indicate major items affected and not to show every device, outlet, fixture, etc. affected by demolition work.
- C. The drawings do not necessarily reflect as-built conditions. The contractor shall visit the jobsite prior to bidding to determine the overall scope of demolition work.
- D. Refer to sections of other Divisions for applicable requirements affecting demolition work.
- E. Refer to Section 260500 for requirements with regard to power outages affecting the operation of existing electrical systems.

1.3 QUALITY ASSURANCE:

A. NEC COMPLIANCE:

1. Comply with applicable portions of NEC as to methods used for demolition work.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 GENERAL:

A. Demolition work shall be laid out in advance to eliminate unnecessary cutting, drilling, channeling, etc. Where such cutting, drilling, or channeling becomes necessary, perform with care, use skilled mechanics of the trades involved. Repair damage to building and equipment. Cutting work of other Contractors shall be done only with the consent of that Contractor. Cutting of structural members shall not be permitted.

3.2 PATCHING AND REPAIR

- A. The Contractor is responsible for all demolition, patching and repair of all finished interior surfaces pertaining to the installation of this particular phase of work. All surfaces shall be finished (painted, etc.) to match the adjacent materials, finishes and colors.
- B. Hard surfaces: Whenever demolition or excavation is required for the installation of the electrical system, it shall be the responsibility of this contractor to make repairs and/or replacements of hard finish surfaces such as concrete, asphalt, roofing, etc.

DEMOLITION 26 4119-1

C. The method of patching and repair shall follow good construction practices and all finished surfaces shall match materials and finish wherein the demolition occurred.

3.3 EXISTING EQUIPMENT

- A. The following is a part of this project and all costs pertaining thereto shall be included in the base bid.
- B. The new electrical equipment and apparatus shall be coordinated and connected into the existing system as required. Auxiliary systems shall comply, unless otherwise specified.
- C. The existing electrical devices, conduit and/or equipment that for any reason obstructs construction shall be relocated. Provide conduit, wiring, junction boxes, etc. as required to extend existing circuits and systems to relocated devices or equipment.
- D. The new fixtures indicated for existing outlets shall be installed in accordance with the fixture specifications.
- E. When installing equipment in the existing building, it shall be concealed.
- F. All existing electrical equipment and systems in portions of the building not being remodeled shall be kept operational, in service and in working condition throughout the entire construction period. Restore any circuits and systems interrupted. Provide temporary panels, temporary wiring and conduit, etc. as required.
- G. Maintain circuit integrity and continuity of all existing circuits and systems that interfere with or are interrupted by remodel work unless those circuits are to be abandoned completely. Maintain all circuits and systems in operation during construction. Provide temporary panels, temporary wiring and conduit, etc. as required.
- H. Existing raceways may be used where possible in place, except as noted. All circuits, conduit and wire that are not used in the remodeled area shall be removed back to the panelboard, where it shall be labeled a spare with circuit number indicated. Re-used raceway shall meet all requirements for new installations.
- I. Obtain permission from the Architect and Owner's representative before penetrating any ceiling, floor, and wall surfaces.
- J. Any and all equipment having electrical connections that require disconnecting and reconnection at the same or another location throughout the course of construction shall be included as part of this contract.

END OF SECTION 26 4119

DEMOLITION 26 4119-2

STAGE LIGHTING & DIMMING SYSTEM

PART 1 - GENERAL

1.1 INTENT:

A. The intent of this specification is to define parameters for furnishing and installing a complete working system to the owner. The system is designed to meet specific operational requirements of Mound Fort Middle School. Performance deviations will not be accepted.

1.2 SCOPE

A. THE SCOPE OF THIS WORK INVOLVES THE FOLLOWING:

- 1. Provide and install (2) 24 circuit relay panels for the Auditorium.
- 2. Provide new 200 amp 120/208V AC power feeders to the new relay panels.
- 3. Provide and install new wiring devices as indicated.
- 4. Provide and install all required control wiring. All components necessary to make the system a working network shall be included in the bid. Actual length of network cabling and system layout shall be verified during the project approval process.

1.3 Drawings:

- A. Drawings shall be furnished as follows:
 - 1. One PDF set of drawings shall be furnished for approval within 30 days of award of contract. Prior to fabrication of equipment, one set shall be returned appropriately marked as the approval document.
 - 2. The installing contractor shall be furnished with up to four sets of B size drawings for his/her use.
 - 3. The owner shall be supplied with two sets of "as-built" drawings at the completion of the installation. These drawings shall be part of an operations and maintenance manual covering all major items installed.

1.4 Quality Assurance

- A. To ensure a uniform installation and single responsibility, the lighting control system shall be provided and warrantied by a single manufacturer. This manufacturer shall have manufactured electronic lighting controls for a minimum of 10 years. Companies who assemble dimming racks or banks from components supplied by others, even if that component is private labeled, are excluded from this bid. Mixing of equipment brands shall not be acceptable.
- B. The manufacturer shall have a factory authorized service provider with at least one full

time manufacturer certified service technician on staff located within 50 miles of the job site. In addition, the manufacturer shall provide a 24-hour service hotline.

1.5 Standards

A. All equipment, where applicable standards have been established, shall be built to the standards of Underwriters Laboratories, Inc., the National Electric Code, and the United States Institute for Theater Technology. Approved equipment shall be so labeled on delivery to the job site.

1.6 Substitutions

- A. The equipment specified is the result of efforts on the part of the owner to select equipment for reliability, ease of maintenance and suitability for the owners' purposes. The base bid shall be for Electronic Theatre Controls, Inc. Equipment manufactured by Strand Lighting, Inc will also be accepted provided it meets the requirements of the specification:
- B. Proposals for equipment from other manufacturers, including those listed above, will be considered provided the equipment is fully digital in operation and sufficient documentation is submitted ten days prior to bid date to establish that it meets these specifications. The price for alternate equipment must be identified as an alternate bid and the amount stated as an addition or deduction to the base bid.
- C. Submittals shall include but not be limited to: complete Bill of Materials; one line control riser that identifies, by product name, all dimming and control equipment as well as wire types and counts; cutsheets on all proposed equipment showing full technical specifications, and a document identifying all deviations from this specification.
- D. Any revision or addition to the wiring required by substitute equipment shall be the responsibility of the substituting contractor. This contractor shall also be responsible for any additional architectural or engineering fees occasioned by the necessity of evaluating alternate proposals.
- E. No exception shall be made to the requirement for optical isolation.
- F. No deviation shall be permitted from the requirement for UL listing.

1.7 Fabrication

A. Fabrication shall begin only after approved drawings and a written notice to proceed have been delivered to the manufacturer at the manufacturer's place of business.

1.8 Energization

A. A qualified engineering representative certified by the manufacturer for system startups shall visit the job site after installation is complete and prior to the energization of the system to inspect, test and adjust the system. She/he shall also at that time instruct the

owners' representatives in the operation and maintenance of the system. These services shall not exceed two days and shall be provided within 21 days written notice by the contractor.

1.9 Warranty

A. Electronic Theatre Controls, Inc. (ETC) warrants to the original owner that for a period of two years from date of energization of a permanently installed system, its products will be free from defects in materials and workmanship under normal use and service.

1.10 Manufacturer Services

A. Service shall be provided directly by the manufacturer and service calls shall be made within 24 hours.

PART 2 - RELAY PANELS

2.1 WALL MOUNT RELAY PANEL

A. General

- 1. The wall mount relay panel shall be the Echo Relay Panel as manufactured by ETC, Inc., or equal
- 2. Relay Panels shall be UL508, UL67, and UL924 Listed, and shall be so labeled when delivered
- 3. Relay Panels shall consist of a main enclosure with 30 pole breaker subpanel, relay/dimmer sub panel, integral control electronics, and a low voltage subpanel for data terminations and provision for accessory cards
 - a. Up to two accessory cards shall be supported per relay panel

B. Mechanical

- 1. The panel shall be constructed of 16-gauge steel. All panel components shall be properly treated and finished in fine-textured, scratch resistant paint
- 2. Relay panels shall be available in 120 and 277 Volt AC configurations
 - a. 120V enclosures shall be 67.5" high by 14.36" wide and 4" deep with a weight not more than 80 pounds
 - b. 277V enclosures shall be 67.5" high by 20" wide and 6" deep with a weight not more than 130 pounds
- 3. The panel shall be capable of being mounted on the surface of a wall or recessed mounted
 - a. 120VAC panels shall support mounting between standard wall stud framing (16-inch on center spacing)

- 4. Choice of panel covers shall be available for surface or recess mount applications. This outer panel shall ship complete with a locking door to limit access to electronics and breakers, breakers
 - Optional center-pin reject security screws shall be available for all accessible screws
 - Recess mount doors shall extend 1" beyond all panel edges to hide wall cut-out
- 5. The unit shall provide interior cover over breaker panel to allow access only to class 2 wiring and prevent direct access to class 1 line voltage components
- 6. The Relay panel shall support up to twenty-four 20-amp single pole circuits made up of relays or 300W phase-adaptive dimmers
 - a. Two and three-pole relay circuits shall be supported at decreased density where each pole constitutes one of the available single-pole circuits. Mixing of circuits in any combination shall be supported
 - b. Panels that do not support an integral dimmer module shall not be acceptable
- 7. Relays shall include integral switches for manual control while power is unavailable to the panel such that critical lighting can be set to an on state, without the need for power to the panel
- 8. Relay output lugs shall accept 6-14AWG copper wire
- 9. Breaker subpanel may include up to twenty-nine 20-amp single pole, up to fourteen 20 amp double pole, or nine three pole breakers as required in any combination up to capacity
- 10. Control wiring for DMX, station bus, and Emergency input terminations shall land on removable headers for contractor installation.

C. User Interface

- 1. The user interface shall contain a graphical display with button pad to include 0-9 number entry, up, down back arrow navigation and enter
- 2. Test shortcut button shall be available for local activation of preset, sequence and set level overrides
- 3. The user interface shall have a power status LED indicator (Blue), a DMX status LED indicator (Green), a network status LED indicator (Green) and an LED indicator (red) for errors
- 4. Ethernet interface shall default to automatic IP through link local and DHCP. Upon receiving IP address, the address of the Network Interface Card (NIC) shall display in the about menu. Static address and settings shall also be possible
- 5. The control interface shall support a USB memory stick interface for uploads of configurations and software updates

D. Functional

- 1. Panel setup shall be user programmable. The control interface shall provide the following relay setup features (per circuit):
 - a. Type (1 pole, 2 pole, or 3 pole)
 - b. Name

- c. Circuit Number
- d. DMX address
- e. sACN address
- f. Space Number
- g. Circuit Modes
 - i. Normal (priority and HTP based activation and dimming)
 - ii. Latch-lock
 - iii. Fluorescent
 - iv. DALI
- h. On threshold level
- i. Off threshold level
- j. Include in UL924 emergency activation
- k. Allow Manual
- 2. Relay panels shall support discrete addressing of each relay. Panels that are restricted to use of start address with sequential addressing and cannot assign each 0-10V output control to any internal relay shall not be acceptable
- 3. The panel shall be capable of switching all relays on or off at once, or in a user-selectable delay per relay using a period of 0.1 to 60 seconds, in 0.1 second increments
- 4. An Ethernet connection shall provide advanced control of relays over streaming ACN (sACN) and transmit status, control override, and measured energy usage per branch circuit via an internal Web UI or central monitoring interface
 - Control electronics shall report the following information per branch circuit.
 - i. Breaker state (On/Off)
 - ii. Breaker state (Open/Closed)
 - iii. Current draw (In Amps)
 - iv. Voltage
 - v. Energy usage
- 5. Built-in Control shall include:
 - a. Ability to record up to 16 presets in each space from the control panel, connected control stations, or timed events
 - b. Presets shall be programmable by recording current levels (as set by DMX or connected control stations), by entering levels on the control panel directly, manually selecting relay state on each relay or a combination of these methods. From the control panel, stations, or timed events it shall be possible to record values for up to 16 zones per space
 - c. Up to 8 spaces in a single rack for total of up to 16 spaces shall be supported per system or system subnet
 - d. Indication of an active preset shall be visible on the control panel display
 - e. One 16-step sequence per space for power up and power down routines

- f. The panel shall have a UL924-listed contact input for use in Emergency Lighting systems. The panel shall respond to the contact input by setting included relays to "on", while setting non-emergency relays "off". Each relay can be selected for activation upon contact input
- g. Upon Data loss the system shall provide options to hold last look infinitely or hold for a configured time period set by the installing technician then fade/switch to the input of the next available priority
- h. Control electronics shall respond directly to control stations for zone, preset, and sequence control. Systems that require secondary control systems for this functionality are not acceptable
- After power loss, electronics shall be capable of holding the system in its previous state until new level data (DMX, architectural presets, sequences and zones, or local overrides) is received to make each relay change state
- 6. The control of lighting and associated systems via real time and Astronomical clock controls
 - a. The relay panel shall allow the activation of presets, sequence, and zone programming of up to 50 time clock events via a built in real and astronomical timeclock
 - b. System time events shall be programmable via the control panel.
 - Time clock events shall be assigned to system day types. Standard day types include: everyday, weekday, weekend, Sunday, Monday, Tuesday, Wednesday, Thursday, Friday and Saturday
 - ii. Time clock events shall be activated based on sunrise, sunset, time of day or periodic event
 - iii. System shall automatically compensate for regions using a fully configurable daylight saving time
 - iv. Presets shall be assigned to events at the time clock
 - c. The time clock shall support event override
 - i. It shall be possible to override the timed event schedule form the face panel of the time clock
 - d. The time clock shall support timed event hold
 - i. It shall be possible to hold a timed event from the face panel of the processor
- 7. The panel shall receive ESTA DMX512-A control protocol. Addressing shall be set via the user interface button keypad with any relay being patched to any DMX control address
 - a. 2,500V of optical isolation shall be provided between the DMX512 inputs and the control electronics as well as between control and power components
 - b. The relays shall respond to control changes (DMX or Stations) in less than 25 milliseconds. DMX512 update speed shall be 40Hz
 - c. Setting changes shall be able to be made across all, some, or just one selected relay in a single action from the face panel

- DMX data loss shall allow for levels/relays to be held for ever or for a specified time before switching to a lower priority source
- e. Initial Panel setup
 - i. The relay panel shall automatically detect the type of relay or dimmer installed in each location without need for manual configuration of the physical arrangement.
 - ii. Quick rack setup shall be available to apply address settings across all circuits for rack number, DMX Start Address, sACN universe, and sACN start address.
 - iii. Emergency Setup Menu shall provide optional delays when emergency is activated or deactivated, and option to turn off non-emergency circuits shall be available. Record function shall allow circuits that are turned on to be added to the emergency setting

E. Electrical

- 1. Relay Panels shall be available to support power input from:
 - a. 120/208V three phase 4-wire plus ground
 - b. 120/240V single phase 3-wire plus ground
 - c. 277/480V, 230/400V and 240/415V three phase. 4-wire plus ground
- 2. Conduit Entry:
 - a. Feeders:
 - i. Top or top-side (upper 6" of either side)
 - ii. Bottom or bottom-side 6" of either side
 - iii. Feeders shall enter through the top or bottom according to the orientation of the enclosure
 - iv. Feeder entry shall be nearest to the location of the feeder lugs or main breaker
 - b. Load:
- Load wiring shall enter through the top or bottom of the enclosure
- ii. Load wiring shall enter through the top/bottom surface nearest to the breaker sub panel
- iii. Load wiring may also enter through left and/or right side provided a low voltage chase is not required through the same area. If class 2 chase is required, a field installable barrier panel shall be provided upon request. When installed, the left or right side of the panel, where the barrier has been installed, shall not permit load wiring
- c. Low Voltage:
 - i. Top or top-side (upper 6" of either side)
 - ii. Bottom or bottom-side (bottom 6" of either side)

- iii. For low voltage conduit entry at the relay end of the cabinet, conduits shall be located at the outer 3" of the top/bottom panel
- iv. Field installed low voltage channel shall be provided separately for installation on the left or right side of the panel to allow class 2 wiring to traverse the panel from top to bottom or bottom to top
- 3. All relays shall be mechanically latching
- 4. The relay shall be capable of switching 20A at up to 300V
- 5. The relay panel shall support a maximum feed size of 200 Amps
- 6. Relay panels shall support main circuit breaker options:
 - Main breaker options shall be optional and available for purchase upon request
 - b. Main breakers shall be field installable
 - c. Main breakers shall be available in 100 and 200 Amps for 120V systems and 150 Amps for 277V systems
 - Series rated SCCR ratings apply as follows with appropriate main breaker:
 - i. 22,000A at 120/240V
 - ii. 10,000A at 100A; 120/208V
 - iii. 10,000A, 22,000 or 42,000 at 200A; 120/208V
 - iv. 14,000A at 150A and 200A; 277V/480V
 - v. 65,000A at 200A; 277V/480V
 - e. Main breakers shall allow the following range of wire sizes:
 - i. 1AWG-300kcmil at 120/240V
 - ii. 3/0 to 300kcmil at 120/208V
 - iii. 6AWG-300kcmil at 277V/480V

F. Relay

- 1. Each relay shall have a manual override switch with on/off status indication
- 2. Relays shall be rated for use with:
 - a. 16A Electronic Ballast loads @ 120, 240 and 277V
 - b. 20A Tungsten loads at 120, 240, and 277V
 - c. 20A 277V Ballast (HID)
 - d. Motor loads with ratings of 20 FLA @ 120V, 17 FLA @ 240V, and 14 FLA @ 277V 100,000A symmetrical SCCR
- 3. Isolation shall be 4000V RMS
- 4. Relays shall be latching state
- 5. Rated Life:
 - a. 1,000,000 mechanical activations
 - b. 100,000 cycles at full resistive load

STAGE LIGHTING & DIMMING SYSTEM 26 5561 - 8

- c. 30,000 cycles full motor, inductive, tungsten, and electronic (LED)
- d. Decreasing loading shall increase the rated life of the relay inversely proportional the square of the load
- 6. Relays shall support reporting of current usage with an accuracy of five percent of the connected load

G. Phase Adaptive Dimmer

- 1. The phase adaptive dimmer module shall be fully rated for loads up to 300W
- 2. By default, phase adaptive dimmers shall automatically detect the required dimming mode based on connected loads and lock the mode in at power-up
- 3. The phase adaptive dimmer shall support tungsten/incandescent, 2-wire fluorescent, line-drive LED, electronic transformer and magnetic transformer loads
 - a. Magnetic transformer loads shall be supported at 120V up to 300W when the connected transformers are loaded to their rated current capacity
- 4. Dimmers that do not support magnetic loads shall not be acceptable
- 5. The panel shall support a maximum phase dimming load of 7,200W f populated fully with (24) 300W dimmer modules. Panels that do not support phase dimmers and relays combined in a single panel shall not be accepted

H. Relay Panel Accessories

- 1. A low voltage 0-10V dimming option shall provide up to 24 0-10v control outputs that are linked to relay circuits within the panel. Each output shall support up to 400mA of current sink per output
- A contact input option shall provide 24 dry contact inputs to be linked for direct or group relay control, to activate a preset, or to activate a sequence. Controller software shall allow for normally open maintained, normally closed maintained, or momentary toggle
- 3. A DALI control option shall provide 24 control loops of broadcast DALI control, with each loop controlling up to 64 DALI devices
- 4. A RideThru option shall provide short-term power backup of control electronics by automatically engaging when power is lost, and recharging when normal power is present
- 5. A tamperproof hardware kit shall be available that provides center reject Torx head screws to prevent access to panel interior by unqualified individuals
- I. Main Breaker options shall be available as specified in Section E.6 Thermal
 - 1. The panel shall be convection cooled. Panels that require the use of cooling fans shall not be acceptable
 - 2. The panel shall operate safely in an environment having an ambient temperature between 32°F (0°C) and 104°F (40°C), and humidity between 5-95% non-condensing

2.2 CONTROL STATIONS

A. Stations

1. The Lighting Control Stations shall be the Unison Heritage UH Series Control Stations as manufactured by Electronic Theatre Controls, Inc., or equal.

B. Mechanical

- 1. Unison Heritage Button and Button/Fader Stations shall operate using up to sixteen programmable faders and twelve programmable buttons.
- 2. All button/fader stations shall be available with white, cream, ivory, gray or black faceplates, fader knobs, and buttons.
 - Manufacturer's standard colors shall conform to the RAL CLASSIC Standard.
- 3. Stations shall have indicators lights at each button or fader.
 - a. Indicators shall be comprised of red, green and blue LED's
 - b. Indicator color and state (steady On, Blink, Off) shall be configured in software, and shall operate relative to the button or fader it is associated with.
- 4. All faceplates shall be designed for flush or surface mounting.
- Station faceplates shall be constructed of ABS plastic and shall use no visible means of attachment.
- 6. Station faceplates shall be indelibly marked for each button or fader function.
- 7. The manufacturer shall supply back boxes for flush mounted half gang stations and for all surface mounted stations.

C. Functional

- 1. The Unison Paradigm Control System shall be designed to allow control of lighting and associated systems via Button, Button/Fader, and Interface or Astronomical time clock controls. System shall allow the programming of presets, sequences, macros and time clock events.
- 2. Station Button, Button/Fader, and Interface) control components shall be designed to operate standard default or custom system functions. Components shall operate default functions unless re-assigned via LightDesigner, the Windows-based configuration program.
- 3. Stations (Button and Button/Fader) shall allow programming of station and component electronic lockout levels via LightDesigner.

D. Electrical

- 1. Unison control station wiring shall be an Echelon® Link power network.
 - a. Link power shall utilize low-voltage Class II unshielded twisted pair, type Belden 8471 or equivalent, and one #14 ESD drain wire (when not installed in grounded metal conduit).
 - b. Touchscreen and Interface stations shall also require (2) #16 AWG stranded wires for 24Vdc operating power. 24Vdc wiring shall be topology free.
 - Network wiring may be bus, loop, home run, star or any combination of these.

 Network insulation displacement connectors shall be provided with all stations.

PART 3 - EXECUTION

3.1 INSTALLATION OF LIGHTING CONTROL EQUIPMENT:

- A. Install a complete stage relay system and components as indicated, in accordance with equipment manufacturer's written instructions, and with recognized industry practices, to ensure that lighting control equipment complies with requirements.
- B. Employ the services of a Factory Authorized Theatrical Dealer/Integrator for complete theatrical systems/fixture purchase and project coordination. Dealer/Integrator shall provide the following services:
 - 1. Attendance at prebid walkthrough(s) to answer questions about theatrical systems.
 - 2. Coordination with electrical contractor throughout full term of project.
 - 3. Review all theatrical low voltage terminations made by the electrical contractor.
 - 4. Review the complete theatrical system(s) prior to energization and supervise the energization of system.
 - 5. Complete programming of the system including all button stations and touchscreens and to ensure all architectural fixtures are dimming smoothly and flicker free down to 1%. one additional site visits shall be provided after the building has been turned over, at six months, to make any changes to the programming that may be required by the Owner.
 - 6. Contractor shall be theatrical installer shall be present at the first tech rehearsal and first performance using the system within Auditorium. Owner will coordinate with contractor 3 weeks in advance for personal trained on the system to help with the show and be onsite in case there are any problems. The theatrical installer shall provide this within their bid.
- C. Comply with requirements of NEC, and applicable portions of NECA's "Standard of Installation" pertaining to general electrical installation practices.
- D. Coordinate with other electrical work, including raceways, and electrical boxes and fittings, as necessary to interface installation of lighting control equipment work with other work. Contractor shall be on site as required, to adjust lighting control units for proper light levels as directed by engineer.
- E. Provide all required drawings for each system identified; show all hardware configurations, panel required schedules and numbering. All panel wiring diagrams and typical wiring diagrams for each component.

3.2 FIELD QUALITY CONTROL:

A. Upon completion of installation and after circuitry has been energized, demonstrate capability and compliance of system with requirements.

B. Where possible, correct malfunctioning units at site, then retest to demonstrate compliance; otherwise, remove and replace with new units, and proceed with retesting.

3.3 MANUFACTURER AUTHORIZED PERSONNEL TRAINING:

A. Building Operating Personnel Training: Train Owner's building personnel in procedures for start up, testing and operating lighting control system equipment. Provide video recorded training for Owners Use